ServSwitch™ Wizard IP

USER GUIDE

LOC REM VNC 100 LNK PWR

CONTENTS

Contents

INSTALLATION

CONFIGURATION

OPERATION

FURTHER INFORMATION

INDEX

1

Further information

Index

Introduction

Thank you for choosing the Wizard IP from Black Box. This intelligent product delivers straightforward setup, secure operation and the ability to fully control one or more computers from almost anywhere.

Remote control via a network connection is nothing new and software-only solutions to facilitate this are commonplace. However, they all present two major drawbacks: a) Special software must be used on all of the computers involved, especially the host, and b) if that host ceases to operate, the remote user is powerless to intervene.

Wizard IP is different and requires only the remote system(s) to run a small utility. The host system can run its usual operating system completely unchanged and needs only to be connected (via its keyboard, video and mouse ports) to the compact Wizard IP box.

It is this external connection to the Wizard IP that keeps the remote user in control. Even in the midst of a system crash, the remote user can still view the host's condition as if sitting next to it. Additionally, when the power switch option is employed, a host system can be remotely rebooted, no matter how badly it has locked-up.

Wizard IP really starts to excel when it is hooked to a suitable KVM switch. Then its robust, secure and adaptable operation is available across up to 128 separate host systems.

Four simultaneous remote users
Wizard IP can support four remote users at any one time. All of these may be connected via the IP network port or one may be linked via the modem/ISDN channel.

Local user
The console port allows control of the system(s) by a keyboard, video monitor and mouse connected directly to the Wizard IP.

Modem or ISDN

Modem/ISDN port
This port offers a connection option that can be used alongside, or instead of, the IP network link. It also offers a backup route should the network fail.

Modem or ISDN

IP network/ Internet

IP network/Internet
The IP port allows direct connection to an Ethernet-based local network and from there onto the wider Internet, as required.

Alternatively, the robust Wizard IP security system will allow direct connection to the outside world.

Main KVM connection

OR

Power switch

Optional power control
Wizard IP provides the opportunity to attach one or more power switches. These control the supply to the host system(s) and allow the remote user to hard reset any system that has suffered a failure.

KVM switch

One host or many
On its own, the Wizard IP provides remote access to one host computer system. However, when linked to a suitable KVM switch, the remote user(s) can easily control up to 128 separate host systems.

BLACK BOX
724-746-5500
ServiSwitch
Wizard IP
LOC REM VNC 100 LNK PWR

3

ServSwitch Wizard IP features - front and rear

Considering its capabilities, the Wizard IP is supplied within a remarkably compact casing. Measuring just 198mm x 120mm x 43mm, it occupies just half of a single (1U) rack space and provides most of its connectors at the rear face. The smart front face features the IP network port and the operation indicators.

IP network port
This intelligent Ethernet port can automatically sense whether it is attached to a 10Mb or 100Mb network.

Power input
Connect the supplied power adapter here.

Power control port
Optionally use this port to control one or more power switches. These allow the remote user to take full control of the host system(s).

Modem port
Optionally use this port to attach either a standard modem or an ISDN adapter. This feature provides an alternative, direct-dial, remote link into the Wizard IP.

Indicators
These six indicators clearly show the key aspects of operation:
- **LOC** Keyboard or mouse data are being received from the local console.
- **REM** Keyboard or mouse data are being received from a remote viewer.
- **VNC** Indicates that a remote viewer is connected and active.
- **100** Indicates the Ethernet network speed (10/100Mbs).
- **LNK** Network link and activity indication.
- **PWR** Power indicator.

Configuration switches
Used for flash upgrades and total reset functions. They are not required under normal circumstances.

KVM console
Connect a keyboard, video monitor and a mouse to these three connectors. These allow you to perform the initial configuration of the Wizard IP. Additionally, you can use these to locally control the connected computer(s).

Computer/KVM Switch
Link these connectors to the keyboard, video and mouse ports of the device to be remotely controlled, either a single computer or a KVM switch. The USB port on the right is for future expansion and is not currently used.

4

What's in the box

Wizard IP

CD-ROM

Four Self-adhesive rubber feet

Power supply and country-specific power lead

KVM cable set

Single unit rack brackets plus four screws

What you may additionally need

Double unit rack brackets
Includes twelve screws
Part number: RMK2004-2

PS/2 cables
One set per connected computer.

Part numbers:
EHN408-0005   *5 feet in length*
EHN408-0010   *10 feet in length*
EHN408-0020   *20 feet in length*

PS/2 to USB flash cables
Required to connect with computers that use a USB port to connect their keyboard and mouse.

Part numbers:
EHN428-0006   *6 feet in length*
EHN428-0016   *16 feet in length*
EHN428-0035   *35 feet in length*

PS/2 to Sun flash cables
Required to connect Sun computers that use a mini-DIN port to connect their keyboard and mouse.

Part numbers:
EHN429-0006   *6 feet in length*
EHN429-0016   *16 feet in length*
EHN429-0035   *35 feet in length*

Slave power switches for connection to Wizard IP or master power switch
(part number: Contact Black Box technical support)

Master power switch for connection to Wizard IP or standalone Ethernet operation (part number: Contact Black Box technical support)

PS/2 to AT-style keyboard converter
(part number: FA212)

PS/2 to 9-pin serial mouse converter
(part number: FA314)

Installation

Mounting

Wizard IP offers three main mounting methods:

- Supplied four self-adhesive rubber feet
- Supplied single unit rack brackets
- Optional double unit rack brackets

Single unit rack brackets

These two brackets (plus four screws), extend the size of the Wizard IP so that it fills the full width of a 1U rack slot.

Double unit rack brackets

This kit comprises four brackets (plus twelve screws) and allows two Wizard IP units to be connected side by side and fitted into a 1U rack slot.

Connections

Installation of the Wizard IP involves a number of basic connections to some or all of the following items:

- Host computer or KVM switch ⇨
- Local keyboard, video and mouse
- IP network port
- Modem/ISDN port
- Power input
- Power control port

Host computer or KVM switch

The Wizard IP can either connect directly to a single host computer or to range of hosts via one or more KVM switches.

To connect a host computer or KVM switch

1 Ensure that power is disconnected from the Wizard IP and the computer or KVM switch to be connected.

   (Note: If it is not possible to switch off devices prior to connection, then a 'Hot plug' procedure is available – see the Hot plugging and mouse restoration section for more details).

2 Connect the plugs at one end of a KVM cable set to the keyboard, video and mouse sockets of the computer or KVM switch (for mouse plug conversion information – see Appendix 7).

Monitor (video)	🖥	Blue
Keyboard	⌨	Purple
Mouse	🖱 or 🖱	Mid green

3 Connect the plugs at the other end of the KVM cable set to the corresponding sockets, collectively labelled as 'COMPUTER/KVM SWITCH', at the rear of the Wizard IP.

Local keyboard, video monitor and mouse

A locally connected keyboard, video monitor and mouse are required during the initial configuration. These are also useful during normal use to allow quick local control of any connected host computers.

To connect a local keyboard, video monitor and mouse

1 Position a suitable keyboard, video monitor and mouse in the vicinity of the Wizard IP such that their cables will easily reach.

2 Connect the keyboard, video monitor and mouse plugs to the sockets, collectively labelled as 'KVM CONSOLE', at the rear of the Wizard IP.

From mouse

From keyboard

From video monitor

IP network port

The Wizard IP provides an autosensing Ethernet IP port that can operate at 10 or 100Mbps, according to the network speed. The Wizard IP is designed to reside quite easily at any part of your network:

- It can be placed within the local network, behind any firewall/router connections to the Internet, or
- It can be placed externally to the local network, on a separate sub-network or with an open Internet connection.

Wherever in the network the Wizard IP is situated, you will need to determine certain configuration issues such as address allocation and/or firewall adjustment to allow correct operation. Please refer to Networking issues within the Configuration chapter for more details.

IMPORTANT: When the Wizard IP is accessible from the public Internet or dial up connection, you must ensure that sufficient security measures are employed.

To connect the IP network port

1 Depending upon where in the network the Wizard IP is being connected, run a category 5e or 6 cable from the appropriate hub or router to the Wizard IP.

2 Connect the plug of the category 5e or 6 cable into the IP port on the front panel of the Wizard IP.

3 Configure the network settings as appropriate to the position of the Wizard IP within the network - see Networking issues for details.

Modem/ISDN port

The Wizard IP provides a serial port specifically for you to connect either a modem or ISDN terminal adapter. This can be used as a primary, secondary or backup access port for remote systems, as best suits your overall configuration.

IMPORTANT: When the Wizard IP is accessible from the public Internet or dial up connection, you must ensure that sufficient security measures are employed.

To connect a modem or ISDN port

1 If possible, disconnect power from the Wizard IP and the modem or ISDN adapter.

2 Connect a suitable serial modem (non-crossover) cable to the serial port on the modem/ISDN adapter.

3 Connect the other end of the serial cable to the port labelled COM1 at the rear of the Wizard IP.

Note: The default serial port speed is 115200K and a standard Hayes-compatible auto-answer string is sent during startup. The default startup string is 'ATZHS0=1'. Both the serial port speed and startup string settings can easily be altered during the local or remote configuration - see Initial configuration for more details. The other serial settings are fixed at: No parity, 8 bit word and 1 stop bit.

Power supply connection

The Wizard IP is supplied with a single power supply and an appropriate country-specific IEC power lead. There is no on/off switch so operation begins as soon as the power supply is connected.

To connect the power supply

1 Connect the low voltage output connector from the power supply unit to the power socket on the rear panel of the Wizard IP.

2 Connect the IEC connector of the supplied country-specific power lead to the socket of the power supply.

3 Connect the power lead to a nearby main supply socket.

Power control port

The Wizard IP provides a serial port for connection to one or more optional power control units. This allows you to control the mains power being supplied to the connected host(s) so that an authorised remote user can, if necessary, perform a complete cold reboot on a failed host system.

The control connector of the first power switch is connected, via serial cable, to the rear panel of the Wizard IP. Any additional power switches are then connected via a 'daisy-chain' arrangement to the first power switch. Each power switch box is then given a unique address and access to each power port (8 ports on each power switch box) is gained using a combination of the switch box address and the port number.

'Daisy-chain' control connections

Power switch boxes

Box 1 — IN / OUT
Box 2 — IN / OUT
Box 3 — IN / OUT
Box 4 — IN

Power to computer
Box 2, port 6 - address: 26

The power ports are connected to the power inputs of each computer and the power switch box(es) are then connected to a mains power supply.

IMPORTANT: Power switching devices have a maximum current rating. It is essential to ensure that the total current drawn by the equipment connected to the power switching device does not exceed the current rating of the power switching device. You must also ensure that the current drawn from any mains socket does not exceed the current rating of the mains socket.

Setting up, configuring and using power switching requires three main steps:

- Connect and address the switch boxes ⇨
- Configure the power strings
- Operate remote power switching

To connect and address the switch boxes
Note: The Wizard IP can be powered on during this procedure, however, the switch boxes should be switched off.

1 Mount up to four switch boxes in positions where they are close to the computers that they will control and not too distant from the Wizard IP (preferably within 2.5 metres).

2 Use a serial cable with an RJ9 and a 9-pin D-type connector (see Appendix 7 for specification). Connect the RJ9 plug to the socket marked 'IN' on the first switch box. Connect the other end to the socket marked 'COM2' on the Wizard IP.

3 For each of the remaining switch boxes (if used), use a serial cable with RJ9 connectors at both ends (see Appendix 7 for specification). Connect one end to the socket marked 'OUT' of the previous box and the other end to the socket marked 'IN' of the next box.

4 Set the addressing switches on each switch box using the two micro switches marked 'Slct' on the front panel. The box connected directly to the Wizard IP is Box 1 and so on, down the daisy-chain line to Box 4 at the end.

Box	Switch 1	Switch 2
1	Off	Off
2	On	Off
3	Off	On
4	On	On

Off = switch upwards
On = switch downwards
Switch 1 is on the left side

5 Connect IEC to IEC power leads between each port and the power input socket of each computer that requires power switching. Carefully note to which power ports, on which boxes, each computer is connected. If server systems have multiple power inputs, then each input must be connected via separate ports, which can be on the same, or different boxes.

6 Connect each box to a suitable mains power input.

Now proceed to the configuration stage covered in the Power switching configuration section within the Configuration chapter.

Configuration

Initial configuration

The initial configuration occurs as two distinct parts:

Part 1 – Local configuration
This part of the configuration takes place using the locally connected keyboard and video monitor. It allows you to set up key basic details, network essentials, modem/ISDN parameters and security key creation.

Part 2 – Remote configuration
This part of the configuration takes place using a remote connection (network or dial-up modem/ISDN). It allows fine tuning of the part 1 configuration items plus the creation of multiple user accounts and host details. Go to Part 2 - Remote configuration.

Part 1 – Local configuration

When you switch on the Wizard IP unit for the first time it will take you (using the locally connected keyboard and video monitor) through a set up sequence consisting of four main screens:

Unit config screen
Allows you to determine a mixture of basic and fundamental setup details such as the keyboard layout, admin password, time and date.

Network config screen
Requires you to configure the various key aspects of the IP network port addressing.

Modem config screen
Allows you to optionally alter the current settings for the serial port that is used to connect a modem or ISDN terminal adapter. The IP addresses are used to emulate a two-port network connection and are suitable for most situations.

Secure keys screen
This screen uses your mouse movements or keyboard inputs to create random data. This unpredictable information is then combined with several other factors to develop the basis of the encryption keys that are used to establish secure remote links.

Controlling the local configuration menus
The local menus use only the keyboard. Use the keyboard arrow keys to move the green highlight indicator to the required position. Then, either type the required information or use the left and right arrows to change multiple choice items, as appropriate.

Problems?
The Wizard IP asks for an unknown admin password
The Wizard IP does not display the configuration sequence

11

To perform the initial local configuration

1 Edit the Unit config screen. The key elements here are:

```
      Wizard IP Unit Config

   Hardware      Rev 1
   Firmware      Version BB2
   Keybd Layout  UK
   Admin Passwd
   Unit Name
   Hot Keys      Ctrl+Alt
   Screensaver   10 mins
   Time          21 : 27 : 31
   Date          15   Apr   2004
   Encryption    Prefer Off

   Screen 1 of 5           Next
```

Admin password
Enter a password of at least six characters that has a mix of letters and numerals. The background colour provides an indication of password suitability and is initially red to indicate that the password is not sufficient. When a password with reasonable strength has been entered it changes to blue.

Time and Date
Set these correctly as all entries in the activity log are time stamped using them.

Encryption
Arrange this setting according to your security requirements. See Encryption settings for a description of the issues and the settings.

When all items are correct, select the Save option to display the next screen.

2 Edit the Network config screen. The key elements here are:

```
     Wizard IP Network Config

   MAC Address  00:0F:58:00:00:04
   Use DHCP     ◄No ►
   IP Address   192.168.42.154
   Net Mask     255.255.255.0
   Gateway
   VNC Port     5900
   HTTP Port    80


   Screen 2 of 5           Next
```

Use DHCP/IP address/Net Mask/Gateway
You need to either set the DHCP option to 'Yes' or manually enter a valid IP address, Net mask and Gateway. See Networking issues for more details.

VNC and HTTP ports
These should remain set to 5900 and 80, respectively, unless they clash with an existing setup within the network. See Networking issues for more details.

When all items are correct, select the Save option to display the next screen.

3 If necessary, edit the Modem config screen.

```
       Wizard IP Modem Config

   Server IP    192.168.3.1◄
   Client IP    192.168.3.2
   Baud Rate    115200
   Init String  ATZHS0=1


            Initialize Port
            Restore Defaults


   Screen 3 of 5           Next
```

The default items here are perfectly adequate for the majority of modem and ISDN terminal adapter installations.

The Server IP and Client IP addresses are used to form an isolated two-device PPP network connection via the dial up link. Their settings are not related to any other 'real' network settings within the Wizard IP.

When all items are correct, select the Save option to display the next screen.

4 Move the mouse and enter changing key sequences within this screen.

```
        Wizard IP Secure Keys

     Random data is required to
     generate encryption keys
     for secure VNC access
     Please move the mouse or
     press keys until the bar
     becomes full
              _
     ►✳--------------------◄

   Screen 4 of 5
```

With every mouse move and keypress, the single dash will move across the screen (unless the same key is pressed repeatedly). Periodically, a new star character will be added to the bar as the random data are accepted as part of the new encryption key. When the bar is full, the final encryption keys for your Wizard IP will be created – this process takes roughly 30 to 40 seconds.

5 Once the secure keys have been calculated the Wizard IP will restart and present a standard logon screen.

```
┌────────────────────────────────────────┐
│                                        │
│                                        │
│   ┌──────────────────────────────┐     │
│   │  ServSwitch Wizard IP Logon  │     │
│   └──────────────────────────────┘     │
│                                        │
│    Username: ◄                         │
│    Password:                           │
│                                        │
│                                        │
│                                        │
│                                        │
└────────────────────────────────────────┘
```

At this stage the username will be 'admin' and the password will be whatever you entered in the first setup screen.

Once the username and password have been accepted, the screen should now show the host computer screen (or, if none is connected, a blank image).

6 To view the options menu: Press Ctrl Alt C. More about hotkeys.
(if the standard hotkeys were altered, use the new hotkeys plus C)

```
┌────────────────────────────────────────┐
│                                        │
│   ┌──────────────────────────────┐     │
│   │  ServSwitch Wizard IP Control │     │
│   └──────────────────────────────┘     │
│                                        │
│      >        Logoff        <          │
│         Restore Mouse Functions        │
│             Configuration              │
│                                        │
│   Access Mode    Shared                │
│   Host           Email server          │
│                                        │
│         Return To Host                 │
│                                        │
└────────────────────────────────────────┘
```

Access mode
Allows you to choose between Shared mode (where all other logged on users can see your operations) and Private mode (where the screens of all other users are blanked).

Logoff
Select to close your current session and display the screensaver.

Restore mouse functions
Select to revive a mouse that has ceased to function correctly. See Hot plugging and mouse restoration for details.

Configuration
Select to gain access to the Unit, Network and Modem configuration screens. Within here you can also reset the Wizard IP to its initial state.

Host
Indicates the currently selected host computer and allows you to select others. This item will be blank unless host details have been set within the remote configuration.

Return to host
Quits the menu and returns to the host screen.

Encryption settings

The Wizard IP offers a great deal of flexibility in its configuration and this extends equally to its encryption settings. Due to the variety of situations in which it might be used and the range of viewer applications that need to view it, a number of settings are available that might not make perfect sense at first glance. However, these settings should allow you to configure the Wizard IP and the viewers to operate as required.

Factors to consider when setting these options might be:

- Do all of the connections and operations require encryption?
- Will some users be using older VNC viewer versions?

Wizard IP encryption settings
The Wizard IP configuration page offers three encryption settings:

- **Always on** - This setting will force all viewers to use encryption. *Note: This setting will preclude any VNC viewer versions that do not support encryption.*
- **Prefer off** - This setting does not enforce encryption unless a viewer specifically requests it. If a viewer has its 'Let server choose' setting, then an un-encrypted link will be set up.
- **Prefer on** - This setting generally enforces encryption unless an earlier viewer version is unable to support it, in which case the link will be un-encrypted. If a viewer has its 'Let server choose' setting, then the link will be encrypted.

Viewer encryption settings
The web browser viewers and VNC viewers (of level 4.0b5S or higher) offer four encryption settings:

- **Always on** - This setting will ensure that the link is encrypted, regardless of the Wizard IP encryption setting.
- **Let server choose** - This setting will follow the configuration of the Wizard IP. If the Wizard IP has 'Always on' or 'Prefer on' set, then the link will be encrypted. If the 'Prefer off' setting is selected at the Wizard IP, then the link will not be encrypted.
- **Prefer off** - This setting will configure an un-encrypted link if the Wizard IP will allow it, otherwise it will be encrypted.
- **Prefer on** - If the Wizard IP allows it, this setting will configure an encrypted link, otherwise it will be un-encrypted.

13

Hot plugging and mouse restoration

It is strongly recommended that you switch off a host computer before attempting to connect it to the Wizard IP. However, if this is not possible then you need to 'hot plug' the computer while it is still running. There is not normally a danger of damage to the computer, however, when mouse communications are interrupted, often they fail to re-initialise when reconnected. The Wizard IP provides a feature to reinstate mouse communications once the necessary connections have been made.

There are two main types of data formats used by current PC mice, these are the older 'PS/2' format and the more recent 'IntelliMouse®' format introduced by Microsoft. These use slightly different data arrangements and it is important to know which type was being used before you hot-plugged the computer to the Wizard IP. The previous setting depends both on the type of mouse and the type of driver, as various combinations of PS/2 and IntelliMouse are possible. Using the incorrect restore function may produce unpredictable results and require the computer to be re-booted.

Which restore setting do I use?

The general rule is that unless both the mouse *and* the driver are *both* IntelliMouse compatible then you need to restore the mouse as 'PS/2'. An IntelliMouse can operate in either mode, whereas a PS/2 mouse cannot.

### Recognising an IntelliMouse-style mouse

The IntelliMouse format was introduced to support, among other features, the scroll wheel function. If the mouse has a scroll wheel, then it is likely to support the IntelliMouse format. If it is a Microsoft-branded mouse, then it will usually state that it is an IntelliMouse on its underside label.

Recognising an IntelliMouse driver

Before hot plugging to the Wizard IP (or afterwards using only keyboard control), access the Windows Control Panel of the computer and select either the *Mouse* option (on Windows NT, 2000 and XP) or the *System* option (on Windows 95, 98, ME). Look for the name of the driver, which will usually include the words *PS/2* or *IntelliMouse*.

To restore mouse operation when hot plugging:

1 Using a KVM cable set, carefully make the keyboard, monitor and mouse connections between the host computer and the ports collectively labelled COMPUTER/KVM SWITCH on the Wizard IP.

2 Using a keyboard and monitor directly connected to the Wizard IP, log on and then press `Ctrl` `Alt` `C` to view the options menu. More about hotkeys

3 Select the 'Restore mouse functions' option to display:

4 Select one of the following options:
   - *Restore Standard Mouse* – if PS/2 mode is required, or
   - *Restore IntelliMouse* – if IntelliMouse mode is required.

5 Select the 'Return to host' option.

6 Move the mouse a short distance and check for appropriate on-screen cursor movement. If the mouse cursor darts erratically around the screen, then cease moving the mouse. This is an indication that the chosen restore function is incorrect. Try again using the other restore function.

Note: The restore functions predict the likely mouse resolution settings but may not restore the exact speed or sensitivity settings that were originally set.

Resetting the configuration

**The Wizard IP asks for an unknown admin password**
This may occur if the Wizard IP has been previously configured. If the existing admin password cannot be discovered, then your only recourse is to perform a factory reset.

To invoke a configuration reset by switch
1 Remove power from the Wizard IP unit.
2 At the rear of the Wizard IP, adjacent to the power input socket, click mini switch 1 to its ON (down) position.
3 Re-apply power to the Wizard IP. On the locally connected monitor you should see a Maintenance menu:

```
        Wizard IP Maintenance

        To upgrade unit, visit:
        http://192.168.42.154

   >    Configure Network    <
        Reset Configuration


    Put option switch 1 up to
    return to normal operation.
```

4 Select the 'Reset configuration' option.
   A warning screen will be displayed. Select the RESET option and press ⏎.

```
        Wizard IP Reset Config

   WARNING: Continuing will cause
   your existing configuration to
   be erased.

   The unit will then reset and
   require re-configuring before
   it can be used.

       DO YOU WISH TO CONTINUE?

   >RESET <              Cancel
```

5 Remove power, return the mini switch 1 to its OFF position and then re-apply power. The locally connected monitor should display the first screen of the initial configuration sequence.

The Wizard IP does not display the configuration sequence
If the Wizard IP has been previously configured it may not automatically display the first of the setup screens. In this case you have two options, either:
- Access the Unit, Network and Serial configuration screens separately, or
- Reset the configuration:

To invoke a configuration reset by main menu
1 Using the locally connected keyboard and screen, log on as the admin user.
2 Select the 'Configuration' option.

```
        Wizard IP Configuration

   >  Unit Configuration  <
      Network Configuration
      Modem Configuration

      Reset Configuration

            Back
```

3 Highlight the 'Reset configuration' option and press ⏎.
   A warning screen will be displayed, select the RESET option and press ⏎.

```
        Wizard IP Reset Config

   WARNING: Continuing will cause
   your existing configuration to
   be erased.

   The unit will then reset and
   require re-configuring before
   it can be used.

       DO YOU WISH TO CONTINUE?

   >RESET <              Cancel
```

4 The Wizard IP will reset and then display the first of the four initial configuration screens.

Part 2 – Remote configuration

The second part of the configuration requires you to log into the Wizard IP from a system via either a network connection or a dial-up connection (via modem or ISDN). In either case there are two types of access applications that you can use:

- The VNC viewer – a small application supplied on the CD-ROM or downloadable from the Wizard IP itself.

or

- A standard browser that supports Java – As soon as a web browser makes contact, the Wizard IP downloads a Java application to it. This allows a viewer window to be opened and operation to commence just as it would with the VNC viewer application.

To perform the remote configuration

1 Use either the VNC viewer or a standard web browser to make remote contact with the Wizard IP – see Connecting to the Wizard IP' for more details.

2 If the username entry is not blanked out, enter 'admin'. Then enter the password that was set during the local configuration stage (if no password was set, then just press ⏎). Once logged in, the Wizard IP will show the video output from the host system (if one is connected), or otherwise a 'No Signal' message.

3 Click the Configure button in the top right hand corner of the window to display the configuration menu ⇩

User accounts
Allows you to create and manage up to sixteen separate user accounts, each with separate access permissions.

Unit configuration
Allows you to alter both basic and fundamental settings within the Wizard IP.

Network configuration
Here you can alter any of the existing network settings plus you can take advantage of the IP access control feature that lets you to specifically include or exclude certain addresses or networks.

Serial port configuration
Lets you setup or alter the details concerning the modem and power control serial ports.

Host configuration
Allows you to configure user access, hot key switching and power control codes for up to 128 host systems that may be connected to the Wizard IP via KVM switch units.

Logging and status
Provides various details about the user activity on the Wizard IP.

Shaded items signify options that are not available at the local configuration stage.

Many of the options within the configuration menu duplicate those that were set (or are available) in the local configuration. However, there are numerous other settings that are only available here.

For more information about each menu option, please see Appendix 5 - Remote configuration menus in the 'Further information' chapter.

Networking issues

Thanks to its robust security the Wizard IP offers you great flexibility in how it integrates into an existing network structure. The Wizard IP is designed to reside either on an internal network, behind a firewall/router or alternatively with its own direct Internet connection.

Positioning Wizard IP in the network

Every network setup is different and great care needs to be taken when introducing a powerful device such as the Wizard IP into an existing configuration. A common cause of potential problems can be in clashes with firewall configurations. For this reason the Wizard IP is designed to be intelligent, flexible and secure. With the minimum of effort the Wizard IP can reside either behind the firewall or alongside with its own separate Internet connection.

Wizard IP situated behind the firewall

Wizard IP situated alongside the firewall

IMPORTANT: When the Wizard IP is accessible from the public Internet or dial up connection, you must ensure that sufficient security measures are employed.

Placing Wizard IP behind a router or firewall

A possible point of contention between the Wizard IP and a firewall can occasionally arise over the use of IP ports. Every port through the firewall represents a potential point of attack from outside and so it is advisable to minimise the number of open ports. The Wizard IP usually uses two separate port numbers, however, these are easily changeable and can even be combined into a single port.

IMPORTANT: The correct configuration of routers and firewalls requires advanced networking skills and intimate knowledge of the particular network. Black Box cannot provide specific advice on how to configure your network devices and strongly recommend that such tasks are carried out by a qualified professional.

Port settings

As standard, the Wizard IP uses two ports to support its two types of viewer:

- **Port 80** for users making contact with a web browser, and
- **Port 5900** for those using the VNC viewer.

When these port numbers are used, VNC viewers and web browsers will locate the Wizard IP correctly using only its network address. The firewall/router must be informed to transfer traffic, requesting these port numbers, through to the Wizard IP.

When a web server is also on the local network

Port 80 is the standard port used by web (HTTP) servers. If the Wizard IP is situated within a local network that also includes a web server or any other device serving port 80 then, if you want to use the web browser interface from outside the local network environment, the HTTP port number of the Wizard IP must be changed.

When you change the HTTP port to anything other than 80, then each remote browser user will need to specify the port address as well as the IP address. For instance, if you set the HTTP port to '8000' and the IP address is '192.168.47.10' then browser users will need to enter:

> http://192.168.47.10:8000

(Note the single colon that separates the IP address and the port number).

The firewall/router would also need to be informed to transfer all traffic to the new port number through to the Wizard IP.

If you need to change the VNC port number

If you change the VNC port to anything other than 5900, then each VNC viewer user will need to specify the port address as well as the IP address. For instance, if you set the VNC port to '11590' and the IP address is '192.168.47.10' then VNC viewer users will need to enter:

> 192.168.47.10::11590

(Note the *double* colons that separate the IP address and port number).

The firewall/router would also need to be informed to transfer all traffic to the new port number through to the Wizard IP.

17

Addressing

When the Wizard IP is situated within the local network, you will need to give it an appropriate local IP address and IP network mask. This is achieved most easily using the DHCP server option which will apply these details automatically. If a DHCP server is not available on the network, then these details need to be applied manually in accordance with the network administrator.

The firewall/router must then be informed to route incoming requests to port 5900 or port 80 (if available) through to the local address being used by the Wizard IP.

Remote user with VNC viewer accesses IP address: 129.7.1.10 and automatically uses port 5900.

Internet

Firewall/router address: 129.7.1.10
The firewall routes the request from the VNC viewer on port 5900 through to the Wizard IP at local address 192.168.0.3

Wizard IP has a local address and net mask, i.e.

IP address: 192.168.0.3

Net mask: 255.255.255.0

To discover a DHCP-allocated IP address

Once a DHCP server has allocated an IP address, you will need to know it in order to access the Wizard IP via a network connection. To discover the allocated IP address:

1 In either the local or remote Network configuration screens, set the 'Use DHCP' option to 'Yes' and select 'Save'. Once the page is saved, the Wizard IP will contact the DHCP server and obtain a new address.

2 Re-enter the same 'Network configuration' screen where the new IP address and network mask should be displayed.

DNS addressing

As with any other network device, you can arrange for your Wizard IP to be accessible using a name, rather than an IP address. This can be achieved in two main ways:

• For small networks that do not have a DNS (Domain Name System) server, edit the 'hosts' files on the appropriate remote systems. Using the hosts file, you can manually link the Wizard IP address to the required name.

• For larger networks, declare the IP address and required name to the DNS server of your local network.

The actual steps required to achieve either of these options are beyond the scope of this document.

18

Placing Wizard IP alongside the firewall

Wizard IP is built from the ground-up to be secure. It employs a sophisticated 128bit public/private key system that has been rigorously analysed and found to be highly secure (a security white paper is available upon request from Black Box). Therefore, you can position the Wizard IP alongside the firewall and control hosts that are also IP connected within the local network.

IMPORTANT: If you make the Wizard IP accessible from the public Internet or from a modem, care should be taken to ensure that the maximum security available is activated. You are strongly advised to enable encryption and use a strong password. Security may be further improved by restricting client IP addresses, using a non-standard port number for access or limiting remote access to dial up connections only.

Ensuring sufficient security
The security capabilities offered by the Wizard IP are only truly effective when they are correctly used. An open or weak password or unencrypted link can cause security loopholes and opportunities for potential intruders. For network links in general and direct Internet connections in particular, you should carefully consider and implement the following:

- Ensure that encryption is enabled.
  By local configuration or by remote configuration.
- Ensure that you have selected secure passwords with at least 8 characters and a mixture of upper and lower case and numeric characters.
  By remote configuration.
- Reserve the admin password for administration use only and use a non-admin user profile for day-to-day access.
- Use the latest Secure VNC viewer (this has more in-built security than is available with the Java viewer). To download the viewer.
- Use non-standard port numbers.
- Restrict the range of IP addresses that are allowed to access the Wizard IP to only those that you will need to use. To restrict IP access.
- Do NOT Force VNC protocol 3.3. Remote configuration.
- Add a further level of inherent security by restricting access only via modem or ISDN dialup.
- Ensure that the computer accessing the Wizard IP is clean of viruses and spyware and has up-to-date firewall and anti-virus software loaded that is appropriately configured.
- Avoid accessing the Wizard IP from public computers.

Security can be further improved by using the following suggestions:

- Use a KVM switch with On-Screen-Display driven security access and an auto-logout (after inactivity) feature to provide a second level of security.
- Place the Wizard IP behind a firewall and use port the numbers to route the VNC network traffic to an internal IP address.
- Review the activity log from time to time to check for unauthorized use.
- Lock your server consoles after they have been used.

A security white paper that gives further details is available upon request from Black Box.

Ports
In this configuration there should be no constraints on the port numbers because the Wizard IP will probably be the only device at that IP address. Therefore, maintain the HTTP port as 80 and the VNC port as 5900.

Addressing
When the Wizard IP is situated alongside the firewall, it will require a public static IP address (i.e. one provided by your Internet service provider).

More addressing information:

Discover DHCP-allocated addresses

DNS addressing

19

Power switching configuration

Power switch configuration comprises two main steps:

- Configure the COM2 serial port to the same speed as used by the power switch box(es) - see Serial port configuration for details.
- Configure power ON and OFF strings for each relevant host computer.

For each power port there needs to be a valid 'Power ON string' and similarly an appropriate 'Power OFF string'. In each case, the strings are a short sequence of characters that combine a port address and a power on or off value.

If a particular computer has more than one power input (and thus requires an equivalent number of power ports to control them), collections of strings can be combined to switch all of the required ports together as a group.

To configure the power sequences for each host computer

1 Using VNC viewer or a browser, log on as the 'admin' user.
2 Click the 'Configure' button in the top right corner.
3 Click the 'Host configuration' option.
4 Click a host entry to display a Host configuration dialog:

```
Host Configuration
Name                 |
Users                *
Hotkey / KVM Port    
Power Control Sequence
Power On             
Power Off            
     OK        Clear        Cancel
```

5 If necessary, configure other parameters (Name, Users, Hot Keys - MORE).
6 Enter the **Power control sequences** in the Power On and Power Off fields ⇨
7 Click OK to close the dialog and then click the Save button in the main Host Configuration window to store the details.

Power control sequences

Note: The settings given below are for the EPS-S8 power switch - other power switches may require different settings. Please refer to your power switch documentation for details about codes required by other power switches.

The structure of each power sequence (OFF and ON) is as follows:

$$Pxy=z\backslash 0D$$

Where:

> **x** is the switch box number,
>
> **y** is the power port number,
>
> **z** is '0' for OFF or '1' for ON, and
>
> **\0D** represents Enter (or Carriage return).

Example 1
To switch ON port 5 of switch box 2, the code would be as follows:

- Power sequence: P25=1\0D

Example 2
To switch OFF port 8 of switch box 3, the code would be as follows:

- Power sequence: P38=0\0D

For details about operating this feature, see **Power control** within the Operation chapter.

To control two or more ports simultaneously
You can control up to four power ports using a single sequence. This is done using the same command structure as shown above, plus a delay command, for each port. Immediately following a port command, insert the characters '*' before the next port command, and so on up to four ports. For instance, to switch on ports 1 and 2 in the first power switch, the command line would be:

    P11=1\0D*P12=1\0D

The KVMADMIN utility

Particularly useful for complex Wizard IP configurations and the control of remote installations, KVMADMIN is a powerful administration tool.

KVMADMIN is based upon the successful VNC viewer and uses the same security system. Rather than a graphical interface usch as the standard viewer, KVMADMIN uses command line control to provide the following administration facilities:

- Discover and adjust the Wizard IP configuration, including host systems,
- Save and restore the Wizard IP configuration,
- Set user names and passwords,
- Download the event log,
- Set custom video modes.

The use of KVMADMIN is strictly limited to the 'admin' user and for security purposes it is not possible to retrieve user names or passwords from the Wizard IP.

To use KVMADMIN you require the IP address and admin password of the Wizard IP unit. The command line is as follows:

kvmadmin <command> <ip address> [<parameters>]

where *<command>* is one of the following:

- -setconfig <config-file>
- -getconfig <config-file>
- -setusers <csv-file>
- -getlog <log-file>
- -gethosts <csv-file>
- -sethosts <csv-file>
- -setmodes <csv-file>

For instance, the command line:

kvmadmin -getconfig kvm1.cfg 192.168.2.1

... downloads the current configuration from the Wizard IP unit at the given address and stores it in the local file *kvm1.cfg*.

Whereas the command line:

kvmadmin -setusers users.csv 192.168.2.1

... configures the usernames and passwords for the same unit from the local file *users.csv.*

For more information about KVMADMIN, please refer to the user notes supplied with the utility.

Performing a flash upgrade

Wizard IP is fully reconfigurable via flash upgrade.

To perform a flash upgrade

1 Using a <u>remote connection</u>, log on as the admin user and access the <u>Unit configuration page</u> to determine the current firmware version of the Wizard IP unit.

2 Visit the Black Box website, locate the downloads section and select an Wizard IP firmware revision that is later than the one currently installed.

3 Power down the Wizard IP unit. At the rear of the unit, adjacent to the power input socket, click mini switch 1 to its ON (down) position.

4 Re-apply power to the Wizard IP. On the locally connected monitor you should see a Maintenance menu:

```
           Wizard IP Maintenance

       To upgrade unit, visit:
         http://192.168.42.154

      >    Configure Network    <
           Reset Configuration



      Put option switch 1 up to
      return to normal operation.
```

Current network address of the Wizard IP

The Maintenance menu should display the current network address of the Wizard IP.

- If the current network address is incorrect then select the 'Configure network' option to change it:

5 Use the web browser (not the VNC viewer) on the previously used remote system, connect to the network address shown in the local Maintenance menu.

6 Follow the on screen instructions to upload the firmware file (previously obtained from the Black Box site) to the Wizard IP.

   IMPORTANT: Wait until the upgrade is complete.

7 When the upload is complete and confirmed on screen, log off the remote system and then power down the Wizard IP.

8 At the rear of the unit, return the mini switch 1 to its OFF position and then re-apply power.

Configure network option

```
           Wizard IP Network Config

    MAC Address  00:0F:58:00:00:04
    Use DHCP        No
    IP Address    192.168.42.154
    Net Mask      255.255.255.0
    Gateway

               OK
```

MAC address
Media Access Control address – this is the unique and unchangeable code that was hard coded within your Wizard IP unit when it was built. It consists of six 2-digit hexadecimal (base 16) numbers separated by colons. A section of the MAC address identifies the manufacturer, while the remainder is effectively the unique electronic serial number of your particular unit.

Use DHCP
When this option is selected, your Wizard IP will attempt to locate a DHCP server on the network. If such a server is located, it will <u>supply three things</u> to the Wizard IP: an IP address, an IP network mask (also known as a Subnet mask) and a Gateway address.

IP address
This is the identity of the Wizard IP within a network. It can either be entered manually or configured automatically using the DHCP option. When the DHCP option is enabled, this entry is greyed out.

Net mask
Also often called the 'subnet-mask', this value is used alongside the IP address to help define a smaller collection (or subnet) of devices on a network. In this way a distinction is made between locally connected devices and ones that are reachable elsewhere, such as on the wider Internet.

Gateway
This is the address of the device that links the local network (to which the Wizard IP is connected) to another network such as the Internet. Usually this is a network switch or router and it will be used whenever a device to be contacted lies outside the local network.

Operation

Connecting to the Wizard IP

The Wizard IP offers you three ways to connect:

- Local connection,
- Remote connection by network link,
- Remote connection by direct dial up (modem or ISDN) link,

...and two types of viewer:

- VNC viewer,
- Standard web browser.

Local connection

The keyboard, video monitor and mouse connected directly to the Wizard IP offer password protected access to the host computer(s).

To make a local connection:

1 Using the keyboard connected directly to the Wizard IP, press any key to exit the screensaver and display the logon prompt.

```
ServSwitch Wizard IP Logon


Username: ←
Password:
```

2 Enter your username and password. Providing you have the correct permissions, the screen will display the currently selected host computer.

To view the local control menu

1 Press and hold the hotkeys (usually `Ctrl` and `Alt`), then press `C` and finally release all three keys.

Note: The `Ctrl` and `Alt` keys when pressed in combination are called 'hotkeys' and they signal to the Wizard IP that you wish to control it, rather than the host computer. However, if these particular hotkeys clash with another device or program, then your administrator may change them to a different combination. If the `Ctrl` `Alt` `C` combination fails to work, then please contact the system administrator for details.

```
ServSwitch Wizard IP Control


>          Logoff          <
      Restore Mouse Functions
          Configuration

Access Mode   Shared
Host          Email server

          Return To Host
```

The local control menu contains numerous options, the most useful of which are:

- **Access mode** - Allows you to select a 'Private' mode in order to prevent other logged on users from viewing your actions on the host computer. Use `→` and `←` to change between modes.
  Note: For the courtesy of other users, this mode should be used sparingly. The admin user has the ability to overrule the private setting.

- **Host** - Where more than one host computer is available via the Wizard IP, this option allows you to easily switch between them. Use `→` and `←` to change between host computers.

- **Return to host** - Quits the control menu and displays the host computer screen.

Local connection (continued)

### To avoid the 'hall of mirrors' effect

IMPORTANT: Never configure a system so that your viewer is viewing itself.

When controlling a host computer using the locally connected keyboard, video monitor and mouse, it is possible to use the VNC viewer or a browser (if the host computer is networked) to create a remote link back to itself. This will set up a 'hall of mirrors' effect, where the computer is viewing itself into infinity.

While technically possible, the Wizard IP unit is not designed to withstand this treatment and could sustain damage.

Remote connections

From a remote system, you connect to the Wizard IP using a viewer and a link. There are two types of viewer and two types of link, which can be used in any combination.

Remote connection by VNC viewer

The VNC viewer is a compact application that runs on your remote system and allows you to view and use the Wizard IP and its host computer(s). VNC viewer is readily available from a number of different sources:

- from the Wizard IP installation CD
- from the Wizard IP itself
- from the RealVNC website

### To connect using the VNC viewer

1 Locate and select the VNC viewer icon ⇨

VNC Viewer

- If you are using a dial up link.

A connection details dialog will be displayed:

Enter the Wizard IP address here and click OK

If required, select the encryption mode - MORE [+]

Options button
Provides a range of viewer and connection settings - MORE [+]

2 In the 'Server:' entry, type the address of the Wizard IP as follows:

v.w.x.y

where *v.w.x.y* is the IP network address, for example 192.168.0.3

- If you have been asked to also enter a port number.

3 Click the OK button. Depending on the options selected, you may need to confirm certain items. A connection attempt will be made and if successful, an authentication dialog will be displayed:

4 Enter your username and password. The viewer window should now open and show the current host computer. *Note: If the Username entry is blanked out then only admin user account is currently defined and only a password is required.*

Remote connection by Web browser

You can use a standard Web browser (supported versions) to gain access to the Wizard IP and its host computer(s). As soon as you make contact with the Wizard IP it will begin downloading a small Java application to your browser, which will be used only for the duration of your connection.

To connect using your Web browser

1 Launch your standard Web browser as usual.

- If you are using a dial up link.

2 In the Address section, type the address of the Wizard IP as follows:

http://v.w.x.y

where *v.w.x.y* is the IP network address, for example 192.168.0.3

- If you have been asked to also enter a port number.

3 Press ⏎. A connection attempt will be made. In the browser window, select the 'Connect using built-in Java VNC viewer' option to download a small application that will temporarily empower your browser (on slow connections the application download can take several tens of seconds to complete). Once complete, a connection details dialog will be displayed:

The previously entered Wizard IP address will be shown here

If required, select the encryption mode - MORE [+]

Options button
Provides a range of viewer and connection settings - MORE [+]

4 Make any necessary option/encryption changes and click the OK button to proceed. Depending on the options selected, you may need to confirm certain items.

5 A second connection attempt will be made and if successful, an authentication dialog will be displayed:

6 Enter your username and password. The viewer window should now open and show the current host computer. *Note: If the Username entry is blanked out then only admin user account is currently defined and only a password is required.*

Using the viewer window

The viewer window gives you the ability to view and control the Wizard IP and its host computer(s). Its operation is almost identical regardless of whether you used the VNC viewer or your Web browser to display it.

The menu bar

The viewer window presents a menu bar similar to that shown below. Certain items within the toolbar are displayed depending upon your access permissions and/or the Wizard IP configuration.

Viewer options
(VNC viewer only)
Click the VNC icon to view the viewer window options.

Controls
Displays a menu of options concerning keyboard, video and mouse operation.

Power
Click to access the power on/off options for the current host computer.

Dialogue area
Indicates your username and the host system that you are currently viewing. This area can also display other messages.

Re-sync mouse
Ensures that the mouse pointer which you move and the mouse pointer on the host system are correctly synchronised.

Auto calibrate
Determines the optimum video and/or mouse settings for the currently selected host computer. This button will flash red when a new host screen is encountered. Click this button when you first visit a new screen.

Hosts
Click to display a list of hosts. Choose an entry to connect to that host computer.

Access mode
Allows you to choose between Shared and Private access modes.

Configure
This option is only available to the admin user and provides access to the main configuration menus.

When using the viewer window

What is the best screen resolution to use?
The best resolution for your computer is one that is larger than the screen of the host computer that you are viewing. This will allow you to see everything without scrolling around, as described next.

How do I navigate around a larger screen?
If the screen that you are viewing has a larger resolution than your viewing window you will need to scroll around to see all items. The viewer window allows you to 'bump scroll' (only in full screen mode). This means that when your mouse cursor bumps against the edge of the screen, the screen image will scroll across automatically.

How do I escape from full screen mode?
Press the F8 button. This button is changeable but is most often set to F8.

Why is the ✛ button flashing red?
This happens when a new host screen is viewed (that has not been viewed before). Click the ✛ button to perform an auto calibration for the screen and the mouse. See Auto calibrate for important information about this feature.

How do I change between host computers?
The best way to change between host computers is to click the 'Hosts' button and then select the required computer by name. See Host selection.

How do I remove traces of moved items from the screen?
When you move an item or window across the screen, sometimes it can leave unsightly trails. These are called *artifacts* and can be particularly prevalent when the connection speed is low. To remove artifacts, click the 'Controls' button and select the 'Refresh screen' option. See Controls.

How do I make the most of a slow connection?
The VNC viewer is slightly better suited to slower connections than the browser viewer because it offers more options. Click the Options button of the VNC viewer when entering the Wizard IP address during log on.

Adjust the Threshold setting
Ensure that the video Threshold setting is set higher than the automatic setting suggests. Tweak this setting manually to ensure the best setting.

Fewer colours
Select the Low (64 colours) mode. The Very low option offers hardly any improvement and looks a lot worse.

Rate limit mouse events
When selected, this mode greatly reduces the mouse movement data that are sent to the host computer. When you move the local mouse, the remote cursor will catch up roughly once per second.

26

Mouse pointers

Both viewers provide a double mouse cursor to help overcome any delays caused by slow connections. When you move your mouse you will see two mouse cursors, a local one that responds immediately to your movements and a second, slower moving, cursor that represents the current mouse position at the host.

For the browser viewer, the local cursor is a typical arrow:

Local cursor

Remote host cursor

For the VNC viewer, the local cursor is a dot:

Local dot cursor

Remote host cursor

Additionally, for fast network connections, the VNC viewer also provides a single mouse mode. See Controls - Single Mouse for details.

Single local cursor

Host selection

The Hosts button on the menu bar provides the quickest and most efficient way to switch between host computers. This is because the button is close at hand, but also because the screen calibration details for each host are reused when this method of switching is used. The alternative is to use KVM switch hotkey combinations or the KVM switch on screen display.

Note: The Hosts button is displayed only when the switching details for two or more computers have been declared within the configuration section by the admin user.

To select a host

1 Click the Hosts button to display a list of computers.

2 Click the required computer name to view and control it.

See Appendix 5 - Host configuration for details about programming new hosts into the Wizard IP ('admin' user status required).

Configure

This option is displayed only when you are logged on as the 'admin' user. When selected it provides access to a wide range of Wizard IP settings.

See Appendix 5 - Remote configuration menus for more details.

Auto calibrate ✛

When you visit a host computer for the very first time, your viewer needs to determine the optimum video and mouse settings for that particular computer. The button will remind you to click it by flashing red when a new computer screen is encountered. Performing this step is important because it can help to decrease unnecessary video information being sent across the link, thus improving overall performance.

Once this has been done, providing you use the 'Hosts' button to switch between host computers, the video settings for each machine will be re-used.

Note: When performing an auto calibration, ensure that the screen image is static (no moving images) and also try to remove any on-screen displays generated by KVM switches (such as host names or menus). This is because they can affect the calibration process and result in a lower overall performance level. For mouse calibration, ensure that there are no application windows located around the upper left corner of the screen. This is because as the mouse calibration takes place, the cursor may change (to match the application as it skims across the window) and this may confuse the calculation. Also ensure that the host system does not have the mouse cursor trails option enabled. Wizard IP cannot calibrate video or mouse when the screen resolution is 1600 x 1200, please select a lower resolution setting on the system.

To auto calibrate the screen and/or mouse

1 Use the Hosts button to select the required computer.

2 Click the ✛ button to display the Calibrate options dialog:

3 Click the required action.

A progress indicator will be displayed while the necessary calculations are made.

```
Calibrate

Calibrating the mouse and video
settings will take several seconds.
Calibration is most effective if the
desktop is static and the top-left
corner is clear of windows, icons, etc.

    Video only          Mouse only
   Video + Mouse          Cancel
```

Upon completion an information dialog will explain the results:

```
Information

Mouse calibration was mostly successful.
Mouse movement is Windows XP Enhanced Mk 1

For best calibration ensure that:
- There is no animation on the screen
- There are no icons or windows at the top-left
- The mouse pointer is not animated
- Pointer trails are not enabled

                    OK
```

Re-synchronise mouse ↖ₖ

If you find that your local mouse pointer and that of the host are not correctly synchronised, use this feature to re-align their movements. This operation is also selectable from the Controls menu.

To re-synchronise the mouse

1 Use the Hosts button to select the required computer.

2 Click the ↖ₖ button and then click OK in the subsequent pop-up message.

Note: If you find that this doesn't work, you may need to perform a mouse calibration again.

Access mode - shared/private

Up to five users can be simultaneously logged-on (four remote users plus one local user) and during normal operation, all are able to see the same view of the currently selected host. If you need to perform a sensitive task that should not be viewed by other users, you can change the access mode to Private. This action blanks the viewer window for all other logged on users.

Note: For the courtesy of other users, this mode should be used sparingly. The admin user has the ability to overrule the private setting.

To change the access mode

1 Click one of the arrow buttons adjacent to the Shared/Private indicator.

`r  | <| Shared |>| ad`

Power control

When configured (and where you have access rights) this option allows you to control the mains power input to the currently selected host computer.

Note: This option is generally used to power cycle remote systems that have failed to respond. Before switching a system off, ensure that all attempts have first been made to power it down through normal means.

To switch a system on or off

1 Use the Hosts button to select the required computer.

2 Click the Power button and then select the Switch on or Switch off option, as appropriate.

`s  | Power |<|`
`Switch On`
`Switch Off`

Controls

When clicked, this button reveals a menu of options concerned with keyboard, video and mouse operation.

Single Mouse

This mode is for fast network connections where the cursor response is sufficient to provide instant visual feedback on the remote screen. When enabled, the cursor is 'captured' within the viewer window until you use the 'escape' hot keys.

To escape from single mouse mode, press F8 and then P. Alternatively, enable and use the mouse button escape sequences - see Advanced unit configuration for details.

The single mouse mode does not require calibration.

Resync Mouse

This option has the same effect as the button on the menu bar and resynchronises the local and remote mouse pointers.

Refresh Screen

This option refreshes the whole screen image to remove any artifacts from moved screen items. This is useful when using very low refresh rates on slow speed communication links.

Mouse Control

This option displays a mouse control dialog and is useful when the remote cursor is failing to respond correctly to your mouse movements, even after using the Resync mouse option.

The mouse control dialog allows you to control the remote mouse cursor using a selection of buttons that you click with your local mouse.

Click to produce a single mouse click for the left, centre or right mouse buttons

Click to produce a continuous mouse click and hold for the left, centre or right mouse buttons

Click to move the remote mouse cursor up, down, left or right

Click to calibrate the remote mouse

Click to display the Restore mouse dialog where you can reinstate a mouse that has failed to operate correctly.
For advice on which mouse type to choose.

29

Keyboard Control

This option displays a keyboard control dialog and is useful for sending keyboard combinations (to the host) that are needed regularly or that are trapped by the Wizard IP.

Keyboard Control

+Ctrl+Alt+Del	Send
+Alt+Tab	Send
+Win	Send
	Send
	Send
	Send
	Send
	Send
Close	

Enter the code here → (input field)

Click to send the code → Send

When entering codes:

+   means press down the key that follows

–   means release the key that follows

+–   means press down and release the key that follows

*   means wait 250ms (note: if a number immediately follows the asterisk, then the delay will equal the number, in milliseconds)

It is automatically assumed that all keys specified will be released at the end, so there is need to specify -Ctrl or -Alt if these keys are to be released together.

See Appendix 8 for a list of key sequence codes that can be used.

Examples:

'Ctrl + Alt 12' would be expressed as: +Ctrl+ Alt+1–1+2

+N means press the 'N' key

+Scroll means press the Scroll lock key

+Space means press the space key

Video Settings
see next page

Info

When selected, this option displays an information dialog showing the current logged on users, the current host, its video mode and its mouse motion details.

Information

```
Logged on users: admin
Host: XP Box
Video mode: vesa 800 x 600 @ 75Hz
Mouse motion: Windows XP Enhanced Mk 1
```

OK

Video Settings

This dialog provides access to all of the key video settings that determine image quality and link performance.

Phase
The phase setting adjusts the alignment of the host video output and the remote system video display to achieve the sharpest image.

Horizontal position
Determines the horizontal position of the host screen image within the viewer window.

Vertical position
Determines the vertical position of the host screen image within the viewer window.

Colour, brightness & contrast
Provides an automatic setting button to optimise these three important video constituents for the current host and connection speed.

```
Video Settings

Threshold              < |  7  | >  Auto
Phase                  < | 12  | >  Auto
Horizontal Position    < | -1  | >  Auto
Vertical Position      < |  0  | >  Auto
Colour Brightness & Contrast   Auto
         Calibrate All
Display Activity 0.00%
  Save                        Cancel
```

Calibrate all
Click to determine the optimum settings for all aspects of video the video connection from the host system.

Threshold
The threshold is effectively a noise filter that differentiates between valid video signals and background noise or interference. This has the effect of reducing unnecessary video signals between the Wizard IP and the remote system, thus improving performance.

Display activity
Indicates the level of video activity currently in progress.

Using automatic configurations
- Every setting can be individually subjected to an automatic configuration (click the appropriate 'Auto' button) and most can also be manually adjusted.
- Use the 'Calibrate All' button to automatically determine the optimum settings for all items.

  Note: Before using the 'Calibrate All' option, if possible, remove on-screen display (OSD) elements generated by any connected KVM switches (such as a host name label or menu). These OSD elements use different video rates to those of the host system(s) and can affect the setting of the automatic threshold value. Wizard IP uses an improved calculation procedure to filter out the effect of these elements. However, best results are obtained when the screen contains only host system information.

  Note: To maximise performance, the threshold level is automatically increased by 50% when a slow link is detected.

  Note: When the Wizard IP is used with one or more CATx switches, the threshold needs to be higher than 32 due to the significant amounts of 'noise' that these switches introduce. The Wizard IP configuration should detect such noise and adjust the threshold accordingly.

Setting the Threshold manually
Occasionally it can be useful to manually adjust the Threshold setting, in order to achieve a setting that best suits your particular requirements.

1. Use the 'Calibrate All' function to ensure that all other settings are optimised.
2. Click the Threshold left arrow button to decrement the setting by one and observe the 'Display Activity' indicator.
3. Repeat step 2 until the Display Activity indicator suddenly rises to a much higher level (i.e. 50%). This will mean that you have reached the noise boundary. At this point, increment the Threshold value by 2 or 3 points to achieve an optimum setting.

Connecting via dial up (modem or ISDN) link

When you use a modem or ISDN link to make the connection, the Wizard IP uses standard network protocols to create a private two-device network. This approach ensures consistency and allows you to use exactly the same VNC viewer or browser to view the hosts systems. This is achieved using PPP (Point to Point Protocol) and means that you need to use a dial-up networking method to initiate the connection. Such software is standard with operating systems such as Windows, Linux and Mac OS.

To initiate a dial up link

1 Using a system that has a modem or ISDN adapter installed, locate the dial-up networking option on your system. Please refer to your system documentation for more information.

2 Using the dial-up networking option, enter the telephone/ISDN number where the Wizard IP can be contacted.

3 Initiate the call and when the link is made, continue with either the standard VNC viewer or browser connection.

   Note: For the viewer network connection address, you must use the IP address that the admin user has set as the Server address (or PPP server IP address) within the Modem configuration screen.

Downloading VNC viewer from the Wizard IP

The Wizard IP has the ability to distribute its own VNC viewer application.

To download the VNC viewer

1 Open your Web browser.

2 Enter the network address where the Wizard IP is situated (in the form: http://192.168.0.3) and make the link.

3 In the opening Wizard IP screen, click the link that offers to download the secure VNC viewer 'from the unit'.

4 Save the download file (vncviewer.exe) to your system.

5 Select and run the downloaded file and then connect to the Wizard IP using the VNC viewer application.

If you need to enter a port number

Usually, when you make a network connection to the Wizard IP (either using the VNC viewer or a Web browser) you simply enter the IP address, i.e. 192.168.0.3. However, if a special configuration is necessary, then you may be asked to specify a port number as well as the IP address.

What is a port?

To enter a port number in a Web browser

1 Enter the required IP address in the usual Address box, i.e. http://192.168.0.3

2 At the end of the IP address, add a single colon and then enter the port number (in this example, the required port number is 8000), i.e. http://192.168.0.3:8000

3 Continue with the standard Web browser instructions.

To enter a port number in VNC viewer

1 Enter the required IP address in the usual 'Server' box, i.e. http://192.168.0.3

2 At the end of the IP address, add two colons and then enter the port number (in this example, the required port number is 115900), i.e. http://192.168.0.3::115900

3 Continue with the standard VNC viewer instructions.

Viewer encryption settings

The web browser viewers and VNC viewers (of level 4.0b5S or higher) offer four encryption options. The resulting actions of certain options depend upon how the Wizard IP to which you are connecting is configured:

- **Always on** - This setting will ensure that the link is encrypted, regardless of the Wizard IP encryption setting.
- **Let server choose** - This setting will follow the configuration of the Wizard IP. If the Wizard IP has a preference to encrypt the link, then it will be so, otherwise the link will not be encrypted.
- **Prefer off** - This setting will configure an un-encrypted link if the Wizard IP will allow it, otherwise it will be encrypted.
- **Prefer on** - If the Wizard IP allows it, this setting will configure an encrypted link, otherwise it will be un-encrypted.

Whenever encryption does take place, the viewer will first need to create the necessary secure key before the connection process can continue.

Supported web browsers

The following web browsers have been tested and found to work correctly with Wizard IP.

Windows
- Internet Explorer 5.50 and above,

   with Microsoft [Java] Virtual Machine (release 5.50).

   with Java Runtime Environment 1.3 or above.

Linux
- Netscape 4.61 and above,

   with Java Runtime Environment 1.1 or above.
- Opera,

   with Java Runtime Environment 1.1 or above.

Further information

This chapter contains a variety of information, including the following:

- Getting assistance - see below
- Troubleshooting - see right
- Appendices
    - Appendix 1 - Local configuration menus
    - Appendix 2 - VNC viewer connection options
    - Appendix 3 - VNC viewer window options
    - Appendix 4 - Browser viewer options
    - Appendix 5 - Remote configuration menus
    - Appendix 6 - Addresses, masks and ports
    - Appendix 7 - Cable specifications
    - Appendix 8 - Hotkey sequence codes
    - Appendix 9 - Supported video modes
- Safety information
- Warranty
- End user licence agreement
- Radio frequency energy statements

Getting assistance

If you are still experiencing problems after checking the list of solutions in the Troubleshooting section then we provide a number of other solutions:

- Email   in the US: **techsupport@blackbox.com**
           in the UK: **techhelp@blackbox.co.uk**

- Phone   in the US: **724-746-5500**
           in the UK: **+44 (0)118 965 6000**

Troubleshooting

Remote network users are unable to contact the Wizard IP
- Check that the correct address is being used by the remote users.
- Check the network settings. Check that the users network address has not been excluded in the IP access control section.
- If the Wizard IP is situated behind a firewall, check that the relevant ports are being allowed through the firewall and are being correctly routed.
- Check the front panel indicators, the LNK indicator should be on. If the network link is a 100Mbps connection, the 100 indicator should also be on.

The remote cursor is not correctly responding to my mouse movements
- Recalibrate the mouse. When doing so, ensure that the host system does not have mouse cursor trails enabled and that the top left corner of the screen is clear of application windows.

When logging on using VNC viewer, I cannot enter a username
- Either, the VNC viewer is an old version (download a new one) or only the admin user has been configured on the Wizard IP.

Appendix 1 - Local configuration menus

This section covers the control menus that are available when you are using the locally connected keyboard, video monitor and mouse.

To access the local configuration menus

- On the locally connected keyboard, simultaneously press `Ctrl` `Alt` `C`.

   Note: If the standard hotkeys (CTRL + ALT) have been changed, then you need to use those keys together with C to access the menus.

```
        ServSwitch Wizard IP Control

            >         Logoff          <
              Restore Mouse Functions
                   Configuration

        Access Mode   Shared
        Host          Email server

                  Return To Host
```

If you are not logged on as the 'admin' user then the Configuration menu will not be available.

Use the Host entry to switch to the required host computer (when a KVM switch is used).

Select the 'Configuration' option to display:

```
          Wizard IP Configuration

          >  Unit Configuration    <
             Network Configuration
             Modem Configuration

             Reset Configuration

                    Back
```

Select the required option:

- [Unit configuration](#)
- [Network configuration](#)
- [Modem configuration](#)
- [Reset configuration](#)

Unit configuration

This page provides access to a selection of both basic and fundamental settings for the Wizard IP.

```
        Wizard IP Unit Config

Hardware      Rev 1
Firmware      Version BB2
Keybd Layout  UK
Admin Passwd  
Unit Name     
Hot Keys      Ctrl+Alt
Screensaver   10 mins
Time          21 : 27 : 31
Date          15   Apr   2004
Encryption    Prefer Off

     Save              Cancel
```

Keybd layout
Use the arrow buttons to match the keyboard layout expected by the host system.

Admin password
Enter the password that will be used to gain administrator access to the Wizard IP. There can only be one admin user and only that user is given access to the configuration menus. The admin password background will be red until a reasonably secure password has been entered, although this is only advisory as any password or no password may be entered.

Unit name
The name entered here will be displayed on the local menus and the remote VNC/browser windows.

Hot keys
Use the left and right arrow keys to select an appropriate hot key sequence for the locally connected keyboard. This sequence is used in combination with other keypresses to access the on-screen menus and to change between hosts. The options are: Ctrl+Alt (default), Ctrl+Shift, Alt+Shift, Alt Gr, Left + Right Alt, Left Ctrl + Alt or Right Ctrl + Alt.

Screensaver
Use the left and right arrow keys to select an appropriate period of inactivity on the local keyboard or mouse before a screensaver is displayed and the user is logged out. This setting applies to local users only and once the screensaver is displayed, for security purposes the user is required to log in again. The timeout period can be selected between 5 minutes and 1 day (24 hours), it cannot be disabled. *Note: The Idle timeout option serves a similar purpose for remote connections.*

Time and date
Use the left and right arrow keys to select the correct time and date. The time entry uses the 24 hour clock notation. The internal real time clock will continue to run for roughly one week without power to the Wizard IP, after that it will be lost and require resetting. Use the up and down arrow keys to move between each of the sections within the time and date entries.

Encryption
Three options are available: Always on, prefer off, prefer on. The one to choose depends on the specific details of your installation - see Encryption settings for details. The use of encryption imposes a slight performance overhead of roughly 10% but is highly secure against third party intrusion.

Network configuration

This page allows you to configure the various aspects of the IP port and its relationship with the local network.

```
         Wizard IP Network Config

MAC Address  00:0F:58:00:00:04
Use DHCP         No
IP Address       192.168.42.154
Net Mask         255.255.255.0
Gateway
VNC Port         5900
HTTP Port        80
         >Clear IP Access Control<

     Save                    Cancel
```

MAC address
Media Access Control address – this is the unique and unchangeable code that was hard coded within your Wizard IP unit when it was built. It consists of six 2-digit hexadecimal (base 16) numbers separated by colons. A section of the MAC address identifies the manufacturer, while the remainder is effectively the unique electronic serial number of your particular unit.

Use DHCP
DHCP is an acronym for 'Dynamic Host Configuration Protocol'. Its function is particularly useful when connecting to medium size or larger networks, such as the Internet. When this option is selected, your Wizard IP will attempt to locate a DHCP server on the network. If such a server is located, it will supply three things to the Wizard IP: an IP address, an IP network mask (also known as a Subnet mask) and a Gateway address. These are not usually granted permanently, but on a 'lease' basis for a fixed amount of time or for as long as the Wizard IP remains connected and switched on. Discover allocations.

IP address
This is the identity of the Wizard IP within a network. The IP address can be thought of as the telephone number of the Wizard IP. Unlike the MAC address, the IP address can be altered to suit the network to which it is connected. It can either be entered manually or configured automatically using the DHCP option. When the DHCP option is enabled, this entry is greyed out.

Net mask
Also often called the 'subnet-mask', this value is used alongside the IP address to help define a smaller collection (or subnet) of devices on a network. In this way a distinction is made between locally connected devices and ones that are reachable elsewhere, such as on the wider Internet. This process helps to reduce overall traffic on the network and hence speed up connections in general.

Gateway
This is the address of the device that links the local network (to which the Wizard IP is connected) to another network such as the Internet. Usually this is a network switch or router and it will be used whenever a device to be contacted lies outside the local network.

VNC port
This is the logical link through which communications with a remote VNC viewer will be channelled (see What is a port?). The default setting is 5900 which is a widely recognised port number for use by VNC software. However, in certain circumstances it may be advantageous to alter this number - see Security issues with ports for more details.

Note: The VNC port and HTTP port can be set to the same port number in order to simplify router and firewall configuration. If this is done then the Wizard IP will "listen" for both types of traffic on the single port.

HTTP port
This is the logical link through which communications with a remote web browser will be channelled. The default setting of 80 is an established standard for web (HTTP – HyperText Transfer Protocol) traffic though this can be changed to suit your local network requirements.

Clear IP access control
This option removes all entries from the IP access control feature within the Wizard IP. The IP access control feature (configurable by a remote admin user) allows certain network address ranges to be denied access to the Wizard IP. If set incorrectly, it is possible to exclude all network users and so this option provides an emergency recovery point.

Modem configuration

This page allows you to configure the COM1 serial port located at the rear of the Wizard IP.

```
        Wizard IP Modem Config

Server IP    192.168.3.1
Client IP    192.168.3.2
Baud Rate    115200
Init String  ATZHS0=1



             Initialize Port
             Restore Defaults

  > Save <                 Cancel
```

Server IP / Client IP
When a user dials into the Wizard IP via a modem or ISDN adapter, the Wizard IP sets up a temporary two-device network using PPP (Point to Point Protocol). For this purpose, both devices must have 'dummy' IP addresses so that they can communicate correctly. These two addresses can be almost anything expressed in the quad octet format (i.e. 192.168.3.1.). However, it is advisable not to make them the same as the real IP addresses used by either the remote system or the Wizard IP.

Baud rate
This option configures the speed of the serial connection between the Wizard IP and a connected modem or ISDN terminal adapter. The default setting is 115200. The other communication settings are fixed as: No parity, 8 bit word, 1 stop bit.

Init string
The codes entered here are used to prepare the connected modem or ISDN terminal adapter for use with the Wizard IP. The default code is a Hayes-compatible string to configure auto answer mode and would be understood by the vast majority of modem/ISDN devices. The code is sent when the Wizard IP is first switched on or whenever the Initialize button is clicked.

Initialize port
When selected, this option sends the characters entered in the 'Init string' field to the connected modem or ISDN terminal adapter.

Restore Defaults
When selected, this option resets the 'Baud rate' and 'Init string' values to their original default settings.

Reset configuration

This option allows you to completely reset the Wizard IP.

```
┌─────────────────────────────────────┐
│      Wizard IP Reset Config          │
│                                      │
│  WARNING: Continuing will cause      │
│  your existing configuration to      │
│  be erased.                          │
│                                      │
│  The unit will then reset and        │
│  require re-configuring before       │
│  it can be used.                     │
│                                      │
│      DO YOU WISH TO CONTINUE?         │
│                                      │
│  >RESET <              Cancel        │
│                                      │
└─────────────────────────────────────┘
```

WARNING: This process will remove all settings and return the unit to use its original state. A complete reconfiguration will be required before it can be used.

To reset the Wizard IP configuration
1 With the RESET option highlighted, press ⏎.
2 The first screen of the initial configuration process will be displayed. See Initial configuration for details.

To get here
1 Use the local keyboard and log on as the 'admin' user.
2 Press [Ctrl] [Alt] [C] (hotkeys may be different).
3 Select 'Configuration'.
4 Select 'Reset configuration'.

Clear IP access control

This option removes all entries from the IP access control feature within the Wizard IP.

What is IP access control?
The IP access control feature (configurable by a remote admin user) allows certain network address ranges to be denied access to the Wizard IP. If set incorrectly, it is possible to exclude all network users and so this option provides an emergency recovery point.

To clear IP access control
1 Use the local keyboard and log on as the 'admin' user.

2 Press `Ctrl` `Alt` `C` (hotkeys may be set differently).

3 Select 'Configuration'.

4 Select 'Network configuration'.

5 Highlight the 'Clear IP access control' option and press ⏎.

```
        Wizard IP Network Config

MAC Address  00:0F:58:00:00:04
Use DHCP          No
IP Address        192.168.42.154
Net Mask          255.255.255.0
Gateway
VNC Port          5900
HTTP Port         80
        >Clear IP Access Control<

    Save                Cancel
```

INSTALLATION

CONFIGURATION

OPERATION

FURTHER
INFORMATION

INDEX

Appendix 2 - VNC viewer connection options

When you are connecting to the Wizard IP using the VNC viewer, a number of options are available.

Click here to access the options

IMPORTANT: If you make any changes to the options given here and wish to retain them for successive connection sessions, you must save the changes. To do this, change to the 'Defaults' tab and click the 'Save as defaults' button.

There are six tabbed pages of options:

Colour/Encoding

Auto select
When ticked, this option will examine the speed of your connection to the Wizard IP and apply the most suitable encoding method. This option is suggested for the majority of installations.

Preferred encoding
There are three manually selectable encoding methods which are accessible when the Auto select option is unticked.

- **ZRLE** – This is a highly compressed method that is best suited to slow modem connections.

- **Hextile** – This method offers better performance than the ZRLE when used over a high speed network because there is no need for the Wizard IP to spend time highly compressing the data.

- **Raw** – This is a primitive, uncompressed method that is mainly used for technical support issues. You are recommended not to use this method.

Colour level
This section allows you to select the most appropriate colour level for the speed of the connection to the Wizard IP. Where the connection speed is slow or inconsistent there will be a necessary compromise between screen response and colour depth.

- **Full** – This mode is suitable only for fast network connections and will pass on the maximum colour depth being used by the host system.

- **Medium (256 colours)** – This mode reduces the host system output to a 256 colour mode and is more suitable for ISDN and fast modem connections.

- **Low (64 colours)** – This mode is suitable for slower modem connections and reduces the host system output to 64 colours.

- **Very low (8 colours)** – This mode provides very rudimentary picture quality and hardly any speed advantage over the 64 colour setting. You are recommended not to use this mode.

41

Inputs

Enable all inputs
When selected, allows keyboard, mouse and clipboard data to be transferred between server and viewer systems.

Disable all inputs (view-only mode)
When selected, prevents control data being passed between server and viewer. Viewer can display the server output, but cannot control it.

Customise
Allows you to select which data can be transferred between server and viewer.

Send pointer events to server
When un-ticked, the VNC viewer will not send mouse movement or click data to the Wizard IP or host system.

Send keyboard events to server
When un-ticked, the VNC viewer will not send keyboard information to the Wizard IP or host system.

Send clipboard changes to server
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

Accept clipboard changes from server
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations, except for retreiving the activity log as desribed in the logging and status section.

Rate-limit mouse move events
When ticked, this feature reduces the mouse movement information that is sent to the Wizard IP and host system. This is useful for slow connections and you will notice that the remote cursor will catch up with the local cursor roughly once every second.

Enable 3-button mouse emulation
This feature allows you to use a 2-button mouse to emulate the middle button of a 3-button mouse. When enabled, press the left and right mouse buttons simultaneously to create a middle button action. You are advised to generally use a 3-button mouse.

Pass special keys directly to server
When ticked, 'special' keys (the Windows key, the Print Screen key, Alt+Tab, Alt+Escape and Ctrl+Escape) are passed directly to the Wizard IP rather than being interpreted locally.

Menu key
This feature allows you to select which function key is used to display the VNC viewer options menu. The menu key is only way to exit from the full screen viewer mode.

IMPORTANT: If you make any changes to the options given here and wish to retain them for successive connection sessions, you must save the changes. To do this, change to the 'Defaults' tab and click the 'Save as defaults' button.

Scaling

No Scaling
No attempt is made to make the screen image fit the viewer window. You may need to scroll horizontally and/or vertically to view all parts of the screen image.

Scale to Window Size
Adjusts the server screen image to suit the size of the viewer window.

Custom Size
Adjusts the server screen image according to the Width and Height settings in the adjacent fields. A drop box to the right of the fields allows you to define the image size by percentage or by pixels, as required.

Preserve Aspect Ratio
When ticked, maintains a consistent ratio between the horizontal and vertical dimensions of the screen image.

Misc

Shared connection (do not disconnect other viewers)
This option does not apply to Wizard IP connections.

Full screen mode
When ticked, the VNC viewer will launch in full screen mode. Use the menu key (usually F8) to exit from full screen mode.

Render cursor locally
This option does not currently apply to Wizard IP connections.

Allow dynamic desktop resizing
When ticked, the viewer window will be automatically resized whenever the host system's screen resolution is altered.

Only use protocol version 3.3
This option does not apply to Wizard IP connections.

**Beep when requested to by the server**
When ticked, your local system will beep in response to any error beeps emitted by the Wizard IP.

Offer to automatically reconnect
When ticked, the viewer will offer to restore a lost connection with the server.

Try Single Sign-On if server allows it
This option does not apply to Wizard IP connections.

IMPORTANT: If you make any changes to the options given here and wish to retain them for successive connection sessions, you must save the changes.
To do this, change to the 'Defaults' tab and click the 'Save as defaults' button.

Identities

This feature helps your VNC viewer to confirm that a revisited Wizard IP is genuine and not another device masquerading as an Wizard IP. The list given will retain the identities of all visited units (that have full security enabled).

When you first make a secure connection to the Wizard IP, the security information for that Wizard IP unit is cached within this Identities tab (i.e. the "identity" is known). The next time that you connect to the Wizard IP, its identity is checked against the stored version. If a mismatch is found between the current and the stored identities then a warning will be issued to you.

If an existing Wizard IP is fully reconfigured then it will need to issued with a new identity. In this case the previous identity, listed in this tab, should be removed so that a new identity can be created on the next connection.

Load / Save

Configuration File - Reload
Allows you to load a configuration file saved from this, or another viewer.

Configuration File - Save
Allows you to save the current settings so that they can be copied from one viewer to another.

Configuration File - Save As...
Allows you to save the current settings under a new name so that they can be copied from one viewer to another.

Defaults - Reload
When clicked, all connection options are returned to the default settings that are currently saved.

Defaults - Save
When clicked, saves the current connection options as the default set that will be used in all subsequent VNC connections.

Appendix 3 - VNC viewer window options

Click the VNC icon in the top left corner of the viewer window (or press F8) to display the window options:

Standard window control items

Full screen
Expands the VNC viewer window to fill the whole screen with no visible window edges or toolbar. Press F8 to re-display this menu.

Single mouse mode (P)
Used for fast network connections where a second, "predictor" cursor is not required.

Ctrl, Alt, Send F8, Send Ctrl-Alt-Del
Sends the selected keypress(es) to the Wizard IP and host system. This is necessary because certain keys and key combinations are trapped by the VNC viewer.

Refresh Screen
Requests data from the server for a complete redraw of the screen image, not just the items that change.

New connection...
Displays the connection dialog so that you can log on to a different Wizard IP or VNC server location.

Options...
Displays the full range of connection options - see Appendix 2 for more details.

Connection info...
Displays various connection and display details.

About...
Displays information about your VNC viewer.

45

Appendix 4 - Browser viewer options

When you are connecting to the Wizard IP using a Web browser, a number of options are available.

Click here to access the options

There are four options pages:

Encoding and colour level

Auto select
When ticked, this option will examine the speed of your connection to the Wizard IP and apply the most suitable encoding method. This option is suggested for the majority of installations.

Preferred encoding
There are three manually selectable encoding methods which are accessible when the Auto select option is unticked.

- **ZRLE** – This is a highly compressed method that is best suited to slow modem connections.
- **Hextile** – This method offers better performance than the ZRLE when used over a high speed network because there is no need for the Wizard IP to spend time highly compressing the data.
- **Raw** – This is a primitive, uncompressed method that is mainly used for technical support issues. You are recommended not to use this method.

Colour level
The colour level is fixed at Medium (256 colours) for almost all browsers.

Inputs

View only (ignore mouse & keyboard)
When ticked, the viewer will not send keyboard or mouse information to the Wizard IP or host system.

Accept clipboard from server
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

Send clipboard to server
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

Security

512 bits (low security)
Selects the lowest level of encoding for communications between the browser and the Wizard IP.

1024 bits (medium security)
Selects the middle level of encoding for communications between the browser and the Wizard IP.

2048 bits (high security)
Selects the highest level of encoding for communications between the browser and the Wizard IP.

Misc

Shared (don't disconnect other viewers)
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

Render cursor locally
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

Fast CopyRect
This feature is restricted to software server versions of VNC and has no effect on Wizard IP installations.

46

Appendix 5 - Remote configuration menus

This section covers the configuration menus that are available to remote admin users using either the VNC viewer or the browser methods of access.

To access the remote configuration menus

- Click the Configure button in the top right corner of the window when logged on as the admin user.

Main configuration menu

Logged on users: admin

User Accounts
Unit Configuration
Network Configuration
Serial Port Configuration
Host Configuration
Logging and Status

Return to Host

Configuration

Logged on users
Indicates the current users irrespective of whether they are connected locally, by modem/ISDN or via a network.

Click the required option
- User accounts
- Unit configuration
- Network configuration
- Serial port configuration
- Host configuration
- Logging and status

User accounts

This section allows you to manage up to sixteen separate accounts.

The first of the sixteen accounts is the admin account and is the only account with access rights to the configuration menus. The user name and access rights are fixed for the admin account, the only change possible for this account is the password.

There are fifteen user account positions.

User Name
All user names must consist of lower case characters or numbers only. No symbols or upper case characters are permissible. The user name can be between 1 and 16 characters in length.

Password
Passwords are case sensitive and can include certain keyboard symbols. The password can be between 1 and 16 characters in length. It is important to note, however, that the password background remains shaded in amber while the Wizard IP considers your entered password to be too easy to guess. A suitable password is best constructed using a mixture of more than 6 letters, numbers and punctuation characters.

Local
When ticked, the selected user can gain access using the local KVM console directly connected to the Wizard IP.

Modem
When ticked, the selected user can gain access via a modem or ISDN link (requires external modem/ISDN equipment to be connected to the Wizard IP).

Remote
When ticked, the selected user can gain access via an IP network link, such as a local intranet or the wider Internet (depending on how the Wizard IP is connected).

Power
When ticked, the selected user will be permitted to control the power input to host systems (requires optional power control switch unit(s) to be fitted).

To create a new account
1 Enter the required User Name to activate that position (the Password and access tick box positions will become editable).
2 Optionally enter a password for the user account.
3 Tick/untick the Local, Modem, Remote and Power options that are appropriate to the user.
4 Click the Save button to register your changes.

Unit configuration

This page provides access to a selection of both basic and fundamental settings for the Wizard IP. Many of the settings displayed here are also accessible through the on-screen menu on the locally attached keyboard, mouse and monitor.

Hardware Version
Indicates the version of the electronic circuitry within the Wizard IP unit.

Firmware Version
Indicates the version of the hardwired software within the Wizard IP flash memory. This may be updated using the flash upgrade procedure.

Host Keyboard Layout
Use the arrow buttons to match the keyboard layout expected by the host system.

Admin Password
Enter the password that will be used to gain administrator access to the Wizard IP. There can only be one admin user and only that user is given access to the configuration menus.

Unit Name
The name entered here will be displayed on the local menus and the remote VNC viewer/browser windows.

Local Hot Key Sequence
Use the arrow buttons to select an appropriate hot key sequence for the locally connected keyboard. This sequence is used in combination with other keypresses to access the on-screen menus and to change between hosts. The options are: Ctrl+Alt (default), Ctrl+Shift, Alt+Shift, Alt Gr, Left + Right Alt, Left Ctrl + Alt or Right Ctrl + Alt.

Screensaver Timeout
Use the arrow keys to select an appropriate period of inactivity before a screensaver is displayed and the user is logged out. This setting applies to local users only and once the screensaver is displayed, for security purposes the user is required to log in again. The timeout period can be selected between 5 minutes and 1 day (24 hours), it cannot be disabled.

Time And Date
Use the arrow keys to select the correct time and date. The time entry uses the 24 hour clock notation. The internal real time clock will continue to run for roughly one week without power to the Wizard IP, after that it will be lost and require resetting.

Encryption
Three options are available: Always on, prefer off, prefer on. The one to choose depends on the specific details of your installation - see Encryption settings for details. The use of encryption imposes a slight performance overhead of roughly 10% but is highly secure against third party intrusion.

Advanced unit configuration

Click this button to display several advanced options that do not normally require alteration.

To get here
1 Using VNC viewer or a browser, log on as the 'admin' user.
2 Click the 'Configure' button in the top right corner.
3 Click the 'Unit configuration' option.
4 Click the 'Advanced unit configuration' option.

Force VNC protocol 3.3
IMPORTANT: The use of this option is not recommended. Protocol 3.3 is a legacy version that does not offer any encryption.

Idle timeout
Determines the period of inactivity on a remote connection before the user is logged out. The idle timeout period can be set to any time span, expressed in minutes. *Note: The* _Screensaver_ *option serves a similar purpose for local connections.*

Protocol timeout
Sets the time period by which responses should have been received to outgoing data packets. If the stated period is exceeded, then a connection is considered lost and terminated.

Mouse Latency Allowance
This option is used during calibration to account for latency delays (caused as signals pass through a device) introduced by some KVM switches from alternative manufacturers.

During calibration, the Wizard IP waits for 40ms after each mouse movement before sampling the next. If a KVM device adds a significant delay to the flow of data, the calibration process can be lengthened or may fail entirely. The value entered here is added to (or subtracted from) the default 40ms sampling time.

Note: You can enter negative values (down to -40) in order to speed up the calibration process when using fast KVM switches. Use this option with caution as it can adversely affect the calibration process.

Mouse rate
Defines the rate at which mouse movement data are transmitted to the system. The default option is 20ms, which equates to 50 mouse events per second. This default rate can prove too fast when passed through certain connected KVM switches from alternative manufacturers. In such cases, data are discarded causing the local and remote mouse pointers to drift apart. If this effect is encountered, increase the mouse rate to around 30ms (data are then sent at a slower rate of 33 times per second).

Background refresh rate
Use the arrow keys to alter the refresh rate for screen images via remote links. This allows you to tailor the screen refresh to suit the network or modem connection speeds. The options are: Slow, Medium, Fast or Disabled. When the disabled option is selected, the remote users will need to manually refresh the screen.

Note: When a low connection speed is detected, the background refresh is automatically disabled, regardless of the settings of this option.

Single Mouse Mode Mouse Switch
Allows you to select the mouse button combination that can be used to exit from single mouse mode (when active). Options are: *Disabled, Middle+Right Button, Middle+Left Button.*

Use VESA GTF
When ticked, the VESA Generalized Timing Formula will be used to help determine the correct input video resolution and timing details. See Appendix 9 for a list of all supported video modes.

50

Network configuration

This page allows you to configure the various aspects of the IP port and its relationship with the local network.

MAC address
Media Access Control address – this is the unique and unchangeable code that was hard coded within your Wizard IP unit when it was built. It consists of six 2-digit hexadecimal (base 16) numbers separated by colons. A section of the MAC address identifies the manufacturer, while the remainder is effectively the unique electronic serial number of your particular unit.

Use DHCP
DHCP is an acronym for 'Dynamic Host Configuration Protocol'. Its function is particularly useful when connecting to medium size or larger networks, such as the Internet. When this option is selected, your Wizard IP will attempt to locate a DHCP server on the network. If such a server is located, it will supply three things to the Wizard IP: an IP address, an IP network mask (also known as a Subnet mask) and a Gateway address. These are not usually granted permanently, but on a 'lease' basis for a fixed amount of time or for as long as the Wizard IP remains connected and switched on. Discover allocations.

IP Address
This is the identity of the Wizard IP within a network. The IP address can be thought of as the telephone number of the Wizard IP. Unlike the MAC address, the IP address can be altered to suit the network to which it is connected. It can either be entered manually or configured automatically using the DHCP option. When the DHCP option is enabled, this entry is greyed out.

IP Network Mask
Also often called the subnet-mask, this value is used alongside the IP address to help define a smaller collection (or subnet) of devices on a network. In this way a distinction is made between locally connected devices and ones that are reachable elsewhere, such as on the wider Internet. This process helps to reduce overall traffic on the network and hence speed up connections in general.

IP Gateway
This is the address of the device that links the local network (to which the Wizard IP is connected) to another network such as the wider Internet. Usually the actual gateway is a network switch or router and it will be used whenever a required address lies outside the current network.

VNC Port
This is the logical link through which communications with a remote VNC viewer will be channelled (see What is a port?). The default setting is 5900 which is a widely recognised port number for use by VNC software. However, in certain circumstances it may be advantageous to alter this number - see 'Security issues with ports' for more details.

HTTP Port
This is the logical link through which communications with a remote web browser will be channelled (see What is a port?). The default setting of 80 is an established standard for web (HTTP – HyperText Transfer Protocol) traffic though this can be changed to suit your local network requirements.

IP Access Control
This section allows you to optionally specify ranges of addresses which will or won't be granted access to the Wizard IP. If this option is left unchanged, then the default entry of '+0.0.0.0/0.0.0.0' ensures that access from all IP addresses will be permitted. See Setting IP access control for details.

51

Setting IP access control

The golden rule with this feature is 'Include before you exclude' or to put it another way 'Arrange *allowed* addresses in the list *before* the *denied* addresses'.

This is because the positions of entries in the list are vitally important. Once a range of addresses is denied access, it is not possible to make exceptions for particular addresses within that range. For instance, if the range of addresses from A to F are denied access first, then the address C could not be granted access lower down the list. Address C needs to be placed in the list before the denied range.

IMPORTANT: This feature should be configured with extreme caution as it is possible to deny access to everyone. If such an error occurs, see Clear IP access control for details about how to regain access.

IP Access Control | Add | Remove | Up | Down | Edit
+0.0.0.0/0.0.0.0

In the list, access control addresses prefixed by '+' are allow entries while those prefixed by '– ' are deny entries.

To get here
1 Using VNC viewer or a browser, log on as the 'admin' user.
2 Click the 'Configure' button in the top right corner.
3 Click the 'Network configuration' option.

To define a new IP access control entry
1 Click the Add button to display a popup dialog:

Host IP Address Filter
Network/Address
Mask
Access   < Allow >
OK   Cancel

Network/Address
Enter the network address that is to be allowed or denied access. If a range of addresses is being specified then specify any one of the addresses within the range and use the Mask entry to indicate the size of the range.

Mask
Enter an IP network mask that indicates the range of addresses that are to be allowed or denied access. For instance, if only a single specified IP address were to be required, the mask entry would be 255.255.255.255 in order to specify a single location. See Calculating the mask for IP access control for details.

Access
Use the arrow buttons to select either 'Allow' or 'Deny' as appropriate.

2 Enter the base network address, the mask and select the appropriate access setting.
3 Click the OK button.

To reorder access control entries
IMPORTANT: When reordering, ensure that any specific allowed addresses are listed higher in the list than any denied addresses. Take care not to invoke any deny access settings that would exclude valid users.
1 In the access control list, click on the entry to be moved.
2 Click the Up or Down buttons as appropriate.

To edit/remove access control entries
1 In the access control list, click on the appropriate entry.
2 Click either the Edit or Remove button as appropriate.

Serial port configuration

This page provides all access to settings concerned with the two serial ports (modem and power control) that are situated at the rear of the Wizard IP.

Modem port

PPP Server IP Address / PPP Client IP Address
When a user dials into the Wizard IP via a modem or ISDN adapter, the Wizard IP sets up a temporary two-device network using PPP (Point to Point Protocol). For this purpose, both devices must have 'dummy' IP addresses so that they can communicate correctly. These two addresses can be almost anything expressed in the quad octet format (i.e. 192.168.3.1.). However, it is advisable not to make them the same as the real IP addresses used by either the remote system or the Wizard IP.

Baud Rate
This option configures the speed of the serial connection between the Wizard IP and a connected modem or ISDN terminal adapter. The default setting is 115200. The other communication settings are fixed as: No parity, 8 bit word, 1 stop bit.

Initialization Sequence
The codes entered here are used to prepare the connected modem or ISDN terminal adapter for use with the Wizard IP. The default code is a Hayes-compatible string to configure auto answer mode and would be understood by the vast majority of modem/ISDN devices. The code is sent when the Wizard IP is first switched on or whenever the Initialize button is clicked.

Initialize
When clicked, this option sends the characters entered in the Initialization sequence field to the connected modem or ISDN terminal adapter.

Restore Defaults
When clicked, this option resets the Baud rate and Initialisation sequence values to their original default settings.

Power control port

Baud Rate
This option configures the speed of the serial connection between the Wizard IP and a connected power control unit. The default setting is 9600 as used by the majority of power units. The other communication settings are fixed as: No parity, 8 bit word, 1 stop bit.

Host configuration

This page provides the opportunity to configure various details for each of the host systems that may be connected to the Wizard IP via one or more KVM switch units. There are 128 entries, each of which can be configured with a name, the permitted users, the hot key combinations required to switch to it and, if required, appropriate power control commands.

Add entry for unrecognised host

When selected, any systems visited that are not specified in the Hosts list, will be added to the list. Use with care when visiting complex cascaded systems.

Erase Host Configuration

Removes all hosts from the list.

To create a new host entry
1 Click one of the host entries to reveal a Host configuration dialog.

Name

Enter the name that will be displayed in the viewer window when you click the Host button.

Users

Select the users that will be permitted to connect to this host. Either enter * to allow all users or a list of users separated by commas (e.g. admin,nigel,andy,steve).

Hotkey / KVM Port

Declare the hot key sequence, or a Port Direct address that will cause the KVM switch to link with the required host system. See Hotkey sequences and Port Direct for details.

A list of valid hotkey codes are given in Appendix 8.

Power On

Enter the code required to make an attached power control unit apply power to the selected host. See Power switching configuration for details.

Power Off

Enter the code required to make an attached power control unit remove power from the selected host. See Power switching configuration for details.

2 Enter the required information in each field.
3 Click the OK button.

Hotkey sequences and Port Direct

Wizard IP allows you to enter commands suitable for any KVM switch in order to choose from up to 128 host systems. These switching commands can take the form of hotkey sequences that emulate standard keypress combinations or, for KVM switches that support the Port Direct format, merely basic port numbers.

Hotkey sequences

Almost any combination of keypresses can be emulated using the following notations:

+   means press down the key that follows;

–   means release the key that follows

+–   means press and then release the key that follows

*   means add a delay. The standard delay period is 250ms, however, if a number immediately follows the asterisk, this will define an alternate delay period (in milliseconds)

A list of permissible keypresses and information about how to abbreviate them are given in Appendix 8.

Notes
* *The entries are not case sensitive.*
* *It is not necessary to specify all keys to be released at the end because they are all released automatically after the last code.*
* *A number of KVM switches from alternative manufacturers use hot key sequences that begin with a press/release of either the Scroll Lock or Ctrl keys. These often require a delay between the initial key press and the channel number to allow the switch to respond. A 500ms delay is usually sufficient.*

Examples

To send the command *Ctrl + Alt 4* you should use the following: *+Ctrl+Alt+4*.

To send the command *Ctrl + Alt 12* you should use the following: *+Ctrl+ALT+–1+2*
(the '+–1' entry causes the 1 key to be pressed and released before the 2 key is pressed).

To send the command *Scroll lock 1 + Enter* (with a 500ms delay) you should use the following: *+–Scr*500+1+Ent*

Port Direct

Port Direct is totally transparent communication system that allows supporting KVM switches and remote access devices to communicate with each other. Using the keyboard connections that link each device, Port Direct allows:

* A controlling device to provide address details of the required port, the user's name and access rights, mouse calibration and video mode information.
* A controlled device to confirm the address and other details of the current port.

Such communication simplifies both the configuration and selection of systems, especially within a complex cascade structure. Port Direct also allows the Wizard IP *Hosts* option to directly control the connected KVM switches and then apply the appropriate video capture and mouse scaling settings. Port Direct provides excellent security control to prevent users from accessing systems for which they do not access rights ('sideways movement') because each unit is fully informed of each user's precise access rights.

Port/host addressing using Port Direct
When adding new computers to the Hosts list, the option '*Add entry for unrecognised host*' is provided to automatically add new entries if a port is visited that does not already have a matching host entry. This is a useful option for simple KVM switch configurations, but should be used with care when complex cascades of switches are being used as it may lead to more host entries being added than are strictly necessary.

Additionally, you can specify the port number of the required system using the same format as if controlling the KVM switch directly. Port numbers MUST be entered within square brackets and can be specified to a maximum of four cascaded levels.

Examples

[16]   selects port 16 and is equivalent to the hotkey sequence *+CTRL+ALT+–1+6*

[4105] selects port 5 on a KVM switch that is cascaded through port group 41 (see your KVM switch manual for more details on cascade port numbering).

Logging and status

This screen provides various details about the user activity on the Wizard IP.

Date and time the event occurred

User name

Access method or remote IP address

Type of event

```
VE                                                    _ □ X

Logged on users: admin

20 Apr 04 17:15:17 192.168.0.2      admin       Clear Log
20 Apr 04 17:26:29 admin            192.168.0.2 Logoff
20 Apr 04 17:27:10 admin            192.168.0.2 Logon
20 Apr 04 17:27:16 admin            192.168.0.2 Logoff
20 Apr 04 17:35:56 admin            local       Logoff
20 Apr 04 19:52:14 admin            192.168.0.2 Logon
20 Apr 04 19:53:54 admin            local       Logon
20 Apr 04 20:08:44 admin            local       Logoff
20 Apr 04 20:38:33 admin            192.168.0.2 Logoff
21 Apr 04 08:43:02                               Power On
21 Apr 04 08:43:13 admin            192.168.0.2 Logon
21 Apr 04 08:43:26 admin            local       Logon
21 Apr 04 08:53:26 admin            local       Logoff
21 Apr 04 09:54:58 admin            192.168.0.2 Logoff
21 Apr 04 09:55:19 admin            192.168.0.2 Logon
21 Apr 04 11:36:20 admin            192.168.0.2 Logoff
21 Apr 04 12:01:41 admin            192.168.0.2 Logon
21 Apr 04 15:26:19 admin            local       Logon
21 Apr 04 17:07:33 admin            local       Logoff
21 Apr 04 17:15:17 admin            192.168.0.2 Logoff
22 Apr 04 09:01:25                               Power On
22 Apr 04 09:29:09 admin            192.168.0.2 Logon
22 Apr 04 09:50:43 admin            local       Logon
22 Apr 04 09:51:36 admin            local       Logoff

   Clear Log    Refresh

               Logging and Status              Back
```

Click to clear all log entries

Click to refresh the list

Click to return to the main menu

To copy and paste the log

You can copy the information listed within the log and paste it into another application.

1 While viewing the log screen, press Ctrl and C, to copy the data into the clipboard.

2 In a text application (i.e. Word, WordPad, Notepad) press Ctrl and V, or right mouse click and 'Paste'.

To get here
1 Using VNC viewer or a browser, log on as the 'admin' user.
2 Click the 'Configure' button in the top right corner.
3 Click the 'Logging and status' option.

Appendix 6 – Addresses, masks and ports

IP address, network masks and ports are all closely linked in the quest for one device to find another across disparate network links.

IP addresses

As a rough analogy, consider how you use the telephone system. The phone number for Black Box in the US is **1-724-746-5500**. This number consists of three distinct parts:

- **1** connects from another country to the US,
- **724** connects into Pennsylvania,
- **746** selects the telephone exchange in Lawrence, and
- **5500** is the unique code for Black Box within Lawrence.

The important parts of the whole number depend on where you are. If you were based in the same local area as Black Box, there would be no point in dialling out of the US, or even out of the area. The only part of the whole number that you are interested in is the final part: **5500**.

In a similar way to the various parts of the telephone number, the four sections (or *Octets*) of every IP address have different meanings or "weights". Consider the following typical IP address:

192.168.142.154

192 is the most global part of the number (akin to the *1* of the phone number) and **154** is the most local (similar to the *5500* unique local code of the phone number).

When two network devices communicate with each other, they always "dial the whole number" regardless of their respective locations in a network. However, they still need to know whether the other device is local to them or not, and this is where the net mask comes into play.

Net masks

The net mask (or sub-net mask) informs a device as to its own position within a network. From this it can determine whether any other device is within the same local network or is situated further afield.

Taking the telephone number analogy given in the IP address section, in order to use the telephone system efficiently, it is vital for you to know your location relative to the person you are calling. In this way you avoid dialling unnecessary numbers.

When one network device needs to talk to another, the first thing that it will do is a quick calculation using its own IP address, the other device's IP address and its own net mask. Suppose a device with address **192.168.142.154** and net mask **255.255.255.0** needed to communicate with a device at address **192.168.142.22**. The sending device would perform several calculations:

1 The net mask is used to determine the local and global parts of the sender's IP address. Where there is 255 in the mask, the corresponding address slips through, where there is a 0, it is blocked.

2 Where the net mask was 0, the corresponding part of the result is also zero - this section is now known to be the local part of the IP address.

3 The same process is carried out for the destination address, again using the sender's net mask. Now the local parts of both addresses have been equalised to zero, because their values are not important in determining whether they are both in the same local network.

4 The results of the two net mask operations are now compared, if they match, the destination is local. If not, then the sender will still use the same full destination IP address but will also flag the message to go via the local network gateway and out into the wider world.

The reason for doing this? It makes the network, as a whole, much more efficient. If every message for every recipient was shoved straight out onto the Internet, the whole thing would grind to a halt within seconds. Net masks keep local traffic just that - local.

Want to know more?

Net masks - the binary explanation

To really understand the operation of a net mask it is necessary to delve deeper into the life blood of computers – *binary*; this is native digital, where everything is either a 1 (one) or 0 (zero), on or off, yes or no.

The net mask operation described on the **previous page** is known as a 'bit-wise AND function'. The example of 255.255.255.0 is handy because the last octet is completely zero and is "clean" for illustrative purposes. However, actual net mask calculations are carried out, not on whole decimal numbers, but bit by bit on binary numbers, hence the term 'bit-wise'. In a real local network, a net mask might be **255.255.255.240**. Such an example would no longer be quite so clear, until you look at the net mask in its binary form:

11111111.11111111.11111111.11110000

In this case, the four zeroes at the end of the net mask indicate that the local part of the address is formed by only the last four bits. If you use the diagram from the previous example and insert the new net mask, it will have the following effect on the final result:

192.168.142.154

255.255.255.240

192.168.142.144

Inside a bit-wise AND function
When you "open up" the last octet of the net mask and look at the binary inside, you can see the last four zero bits preventing any 1's in the address from falling through.

.154 → **Decimal octet prior to AND operation with net mask**

10011010 → **Binary equivalent of 154**

1 1 1 1 0 0 0 0   240

10010000 → **Binary octet after AND operation with net mask**

.144 → **Decimal equivalent of 10010000**

Thus, when 154 is *bit-wise ANDed* with 240, the result is 144. Likewise, any local address from 192.168.142.**144** through to 192.168.142.**159** would produce exactly the same result when combined with this net mask, hence they would all be local addresses. However, any difference in the upper three octets or the upper four bits of the last octet would slip through the mask and the address would be flagged as not being local.

Calculating the mask for IP access control

The IP access control function uses a standard IP address and a net mask notation to specify both single locations and ranges of addresses. In order to use this function correctly, you need to calculate the mask so that it accurately encompasses the required address(es).

Single locations

Some of the simplest addresses to allow or deny are single locations. In this case you enter the required IP address into the 'Network/Address' field and simply enter the 'Mask' as **255.255.255.255** *(255 used throughout the mask means that every bit of the address will be compared and so there can only be one unique address to match the one stated in the 'Network/Address' field)*.

All locations

The other easy setting to make is ALL addresses, using the mask **0.0.0.0** As standard, the IP access control section includes the entry: **+0.0.0.0/0.0.0.0** The purpose of this entry is to *include* all IP addresses. It is possible to similarly *exclude* all addresses, however, take great care not to do this as you instantly render all network access void. There is a recovery procedure should this occur.

Address ranges

Although you can define ranges of addresses, due to the way that the mask operates, there are certain restrictions on the particular ranges that can be set. For any given address you can encompass neighbouring addresses in blocks of either 2, 4, 8, 16, 32, 64, 128, etc. and these must fall on particular boundaries. For instance, if you wanted to define the local address range:

192.168.142.67 to **192.168.142.93**

The closest single block to cover the range would be the 32 addresses from:

192.168.142.64 to **192.168.142.95**.

The mask needed to accomplish this would be: **255.255.255.224**

When you look at the mask in binary, the picture becomes a little clearer. The above mask has the form: **11111111.11111111.11111111.11100000**

Ignoring the initial three octets, the final six zeroes of the mask would ensure that the 32 addresses from .64 (01000000) to .95 (01011111) would all be treated in the same manner. See Net masks - the binary explanation for details.

When defining a mask, the important rule to remember is:

   There must be no 'ones' to the right of a 'zero'.

For instance, (ignoring the first three octets) you could not use a mask that had 11100110 because this would affect intermittent addresses within a range in an impractical manner. The same rule applies across the octets. For example, if you have zeroes in the third octet, then all of the fourth octet must be zeroes.

The permissible mask values (for all octets) are as follows:

Mask octet	Binary	Number of addresses encompassed
255	11111111	*1 address*
254	11111110	*2 addresses*
252	11111100	*4 addresses*
248	11111000	*8 addresses*
240	11110000	*16 addresses*
224	11100000	*32 addresses*
192	11000000	*64 addresses*
128	10000000	*128 addresses*
0	00000000	*256 addresses*

If the access control range that you need to define is not possible using one address and one mask, then you could break it down into two or more entries. Each of these entries could then use smaller ranges (of differing sizes) that, when combined with the other entries, cover the range that you require.

For instance, to accurately encompass the range in the earlier example:

192.168.142.67 to **192.168.142.93**

You would need to define the following six address and mask combinations in the IP access control section:

Network/address entry	Mask entry	
192.168.142.67	255.255.255.255	*defines 1 address (.67)*
192.168.142.68	255.255.255.252	*defines 4 addresses (.68 to .71)*
192.168.142.72	255.255.255.248	*defines 8 addresses (.72 to .79)*
192.168.142.80	255.255.255.248	*defines 8 addresses (.80 to .87)*
192.168.142.88	255.255.255.252	*defines 4 addresses (.88 to .92)*
192.168.142.93	255.255.255.255	*defines 1 address (.93)*

Ports

If you accept the analogy of IP addresses being rather like telephone numbers, then think of ports as extension numbers. In a company of any size, you generally wouldn't expect the accounts department to share the same telephone with the technical department. Although their calls may all be related to the same company, they concern very different aspects of that company.

It is the same with IP network connections. Although you have only one network link into your computer and only one IP address (phone number), you are probably performing many different tasks through that one link, often at the same time. Thus, when you browse the web your outgoing requests and the incoming information are all channelled through port 80. When you send an email, it travels through port 25 and when you transfer files you are, without knowing it, using port 20.

At the "border crossing" between the wider Internet and every local network attached to it, there is a router that is usually combined with a firewall. One of its main tasks is to direct incoming traffic to the correct place within its local network. A key piece of information to help it do this is the port number:

Security issues with ports

The settings of port numbers become important when the Wizard IP is situated behind a network firewall. In order for a remote VNC viewer or web browser to make contact with your Wizard IP, it is necessary for the firewall to allow communication through a particular numbered port to occur.

One specific function of firewalls is to restrict access to ports in order to prevent malicious attackers using them as a route into your network. Every new port that is opened offers a new possibility for hackers and so the number of accessible ports is purposefully kept to a minimum. In such cases, it may be advantageous to change one or both Wizard IP ports to use the same number. The other alternative is to place the Wizard IP unit outside the firewall and take full advantage of its secure operation features – see Networking issues for details.

IMPORTANT: The correct configuration of routers and firewalls requires advanced networking skills and intimate knowledge of the particular network. Black Box cannot provide specific advice on how to configure your network devices and strongly recommend that such tasks are carried out by a qualified professional.

User accesses the company website at: 129.7.1.10 (this automatically uses port 80).

Internet

User with VNC viewer accesses IP address: 129.7.1.10 (this automatically uses port 5900).

Router/firewall address: 129.7.1.10
Router is programmed to send port 5900 VNC traffic to local address 192.168.0.3 and port 80 web traffic to local address 192.168.0.42

Wizard IP has the local IP address: 192.168.0.3

Web server

Web server has the local IP address: 192.168.0.42

Appendix 7 – Cable and connector specifications

RS232 serial mouse to PS/2 converter cable

6pin mini-DIN female			9pin D-type female
CLK	5	1	DCD
DAT	1	2	RXD
TXD	2	5	GND
GND	3	4	DTR
+5V	4	6	DSR
-12V	6	7	RTS
		3	TXD (-12V)
		8	CTS
		9	RI

NC — 1 DCD
NC — 8 CTS
NC — 9 RI

Female
5 6
3 4
1 2

Wizard IP to power switch cable

9pin D-type female			4pin RJ9
TXD	2	3	RXD
RXD	3	2	TXD
GND	5	1	GND
		4	GND

Power switch to power switch daisy chain cable

4pin RJ9			4pin RJ9
GND	1	1	GND
TXD	2	2	TXD
RXD	3	3	RXD
GND	4	4	GND

Appendix 8 – Hotkey sequence codes

These codes are used when defining hotkey switching sequences (macros) for host computers and allow you to include almost any of the special keys on the keyboard.

Permissible key presses

Main control keys *(see 'Using abbreviations')*
Backspace | Tab | Return | Enter | Ctrl | Alt | Win | Shift | LShift | RShift
LCtrl | RCtrl | LAlt | AltGr | RAlt | LWin | RWin | Menu | Escape | Space
CapsLock | NumLock | PrintScreen | Scrolllock

Math operand keys *(see 'Using abbreviations')*
Add (Plus) | Subtract (Minus) | Multiply

Central control keys *(see 'Using abbreviations')*
Insert | Delete | Home | End | PageUp | PageDown
Up | Down | Left | Right | Print | Pause

Keypad keys *(see 'Using abbreviations')*
KP_Insert | KP_Delete | KP_Home | KP_End | KP_PageUp
KP_PageDown | KP_Up | KP_Down | KP_Left | KP_Right | KP_Enter
KP_Add | KP_Subtract | KP_Divide | KP_Multiply
KP_0 to KP_9

Function keys
F1 | F2 | F3 | F4 | F5 | F6 | F7 | F8 | F9 | F10 | F11 | F12

ASCII characters
All characters can be entered using their ASCII codes, from 32 to 126 (i.e. A,B,C,
… 1,2,3 etc.) with the exception of the special characters '+', '-', '+−' and '*'
which have special meanings, as explained below.

Codes with special meanings
+   means press down the key that follows

–   means release the key that follows

+−   means press down and release the key that follows

*   means wait 250ms (note: if a number immediately follows the asterisk, then
     the delay will equal the number, in milliseconds)

Note: Hotkey sequences are not case sensitive.

Creating macro sequences

Hot key macro sequences can be up to 256 characters long. All keys are assumed to be released at the end of a line, however, you can also determine that a key is pressed and released within a sequence. Any of the following three examples will send a command that emulates and a press and release of the Scroll Lock key:

+SCROLL-SCROLL
+-SCROLL
+SCROLL-

Example:

+-SCROLL+-SCROLL+1+ENTER

Press and release scroll twice, press 1 then enter then release all keys (equivalent definition is +SCROLL-SCROLL+SCROLL-SCROLL+1+ENTER-1-ENTER)

Using abbreviations
To reduce the length of the key definitions, any unique abbreviation for a key can be used. For example: "scroll", "scr" and even "sc" all provide an identifiable match for "ScrollLock" whereas "en" could not be used because it might mean "Enter" or "End" ("ent" would be suitable for "Enter").

Note: Hotkey sequences and abbreviations are not case sensitive.

For information about where to enter these codes, please see the sections Host configuration or Keyboard control.

Appendix 9 – Supported video modes

The following video modes are supported and can be automatically configured by the Wizard IP. If a recognised video mode cannot be found, the Wizard IP will gradually change some of the key parameters to discover whether a video lock can be achieved. Support for VESA GTF (Generalized Timing Formula) is available and can be enabled via the Advanced Unit Configuration screen.

The half width video modes capture every other pixel. These are not generally recommended for normal use but may be used for emergency access to high resolution, high frequency system screens. Half width screens can be expanded to normal width using the scaling features of the viewer.

vesa 720 x 400 @ 85Hz	sun 1152 x 900 @ 66Hz
vesa 640 x 480 @ 60Hz	sun 1152 x 900 @ 76Hz
vesa 640 x 480 @ 72Hz	sun 1280 x 1024 @ 67Hz
vesa 640 x 480 @ 75Hz	
vesa 640 x 480 @ 85Hz	apple 640 x 480 @ 67Hz
vesa 800 x 600 @ 56Hz	apple 832 x 624 @ 75Hz
vesa 800 x 600 @ 60Hz	apple 1152 x 870 @ 75Hz
vesa 800 x 600 @ 72Hz	
vesa 800 x 600 @ 75Hz	1900 x 1200 @ 60Hz**
vesa 800 x 600 @ 85Hz	
vesa 1024 x 768 @ 60Hz	
vesa 1024 x 768 @ 70Hz	
vesa 1024 x 768 @ 75Hz	
vesa 1024 x 768 @ 85Hz	
vesa 1152 x 864 @ 75Hz	
vesa 1280 x 960 @ 60Hz	
vesa 1280 x 1024 @ 60Hz	
vesa 1280 x 1024 @ 75Hz	
vesa 1600 x 1200 @ 60Hz	
vesa 1600 x 1200 @ 65Hz half-width	
vesa 1600 x 1200 @ 70Hz half-width	
vesa 1600 x 1200 @ 75Hz half-width	
vesa 1600 x 1200 @ 85Hz half-width	
vesa 720 x 400 @ 70Hz*	

* Not actually a VESA mode but a common DOS/BIOS mode

** May also work on some systems when the operating temperature of the Wizard IP is controlled.

Safety information

- For use in dry, oil free indoor environments only.

- Warning - live parts contained within power adapter.

- No user serviceable parts within power adapter - do not dismantle.

- Plug the power adapter into a socket outlet close to the module that it is powering.

- Replace the power adapter with a manufacturer approved type only.

- Do not use the power adapter if the power adapter case becomes damaged, cracked or broken or if you suspect that it is not operating properly.

- If you use a power extension cord with the Wizard IP, make sure the total ampere rating of the devices plugged into the extension cord does not exceed the cord's ampere rating. Also, make sure that the total ampere rating of all the devices plugged into the wall outlet does not exceed the wall outlet's ampere rating.

- Do not attempt to service the Wizard IP yourself.

Safety considerations when using power switches with Wizard IP

- Follow the manufacturer's instructions when setting up and using power switching products.

- Always ensure that the total ampere rating of the devices plugged into the power switching product does not exceed the power switching product's ampere rating. Also, make sure that the total ampere rating of all the devices plugged into the wall outlet does not exceed the wall outlet's ampere rating.

General Public License (Linux)

The Wizard IP runs an embedded version of the Linux operating system, licensed under the GNU General Public License. To obtain the source code for the open-source components of the system visit:

http://www.realvnc.com/products/WizardIP/gpl.html.

End user licence agreement

PLEASE READ THIS AGREEMENT CAREFULLY. THIS AGREEMENT CONCERNS ENHANCED VNC VIEWER SOFTWARE ("the SOFTWARE") FOR USE WITH THE Wizard IP PRODUCT ("the PRODUCT"). THE SOFTWARE IS PROVIDED TO ENABLE YOU TO OPERATE THE PRODUCT. BY USING ALL OR ANY PORTION OF THE SOFTWARE YOU ACCEPT ALL THE TERMS AND CONDITIONS OF THIS AGREEMENT. IF YOU DO NOT ACCEPT ALL THE TERMS AND CONDITIONS OF THIS AGREEMENT THEN DO NOT USE THE SOFTWARE. BY USING ANY UPDATED VERSION OF THE SOFTWARE WHICH MAY BE MADE AVAILABLE, YOU ACCEPT THAT THE TERMS OF THIS AGREEMENT APPLY TO SUCH UPDATED SOFTWARE.

1.   Intellectual Property Rights

The Software and its structure and algorithms are protected by copyright and other intellectual property laws, and all intellectual property rights in them belong to RealVNC Limited ("RealVNC"), a United Kingdom Limited Company, or are licensed to it. You may not reproduce, publish, transmit, modify, create derivative works from, publicly display the Software or part thereof. Copying or storing or using the Software other than as permitted in Clause 2 is expressly prohibited unless you obtain prior written permission from RealVNC.

2.   Permitted and Prohibited Uses

2.1   During the term of this Agreement and as long as you comply with the terms of this agreement, you may use the Software only with the Product for your personal use or for the internal use of your business. You may make as many copies of the Software as you require for your own internal business purposes only and for archival purposes. You are expressly prohibited from distributing the Software in any format, in whole or in part, for sale, or for commercial use or for any unlawful purpose.

2.2   You may not rent, lease or otherwise transfer the Software or allow it to be copied. Unless permitted by law, you may not reverse engineer, decompile or disassemble the Software.

3.   Warranty

REALVNC DOES NOT WARRANT ANY RESULTS OBTAINED USING THE SOFTWARE. TO THE EXTENT PERMITTED BY LAW, REALVNC DISCLAIMS ALL OTHER WARRANTIES ON THE SOFTWARE, EITHER EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE IMPLIED WARRANTIES OF MERCHANTABILITY, NON-INFRINGEMENT OF THIRD PARTY RIGHTS AND FITNESS FOR PARTICULAR PURPOSE.

4.   Limitation on Liability

UNDER NO CIRCUMSTANCES SHALL REALVNC BE LIABLE FOR ANY CONSEQUENTIAL INDIRECT OR INCIDENTAL DAMAGES WHATSOEVER INCLUDING LOST PROFITS OR SAVINGS ARISING OUT OF THE USE OF THE SOFTWARE, THE SERVICE OR THE INFORMATION, RELIANCE ON THE DATA PRODUCED OR INABILITY TO USE THE SOFTWARE, THE SERVICE OR THE INFORMATION EVEN IF REALVNC HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. BECAUSE SOME STATES AND COUNTRIES DO NOT ALLOW THE EXCLUSION OR LIMITATION OF LIABILITY FOR CONSEQUENTIAL OR INCIDENTAL DAMAGES, THE ABOVE LIMITATION MAY NOT APPLY TO YOU.

NOTHING IN THIS AGREEMENT LIMITS LIABILITY FOR DEATH OR PERSONAL INJURY ARISING FROM A PARTY'S NEGLIGENCE OR FROM FRAUDULENT MISREPRESENTATION ON THE PART OF A PARTY

5.   Export Control

The United States and other countries control the export of Software and information.   You are responsible for compliance with the laws of your local jurisdiction regarding the import, export or re-export of the Software, and agree to comply with such restrictions and not to export or re-export the Software where this is prohibited. By downloading the Software, you are agreeing that you are not a person or entity to which such export is prohibited.

6.   Term and Termination

This licence shall continue in force unless and until it is terminated by RealVNC by e-mail notice to you, if it reasonably believes that you have breached a material term of this Agreement

In the case above, you must delete and destroy all copies of the Software in your possession and control and overwrite any electronic memory or storage locations containing the Software.

7.   General Terms

7.1   The construction, validity and performance of this Agreement shall be governed in all respects by English law, and the Parties agree to submit to the exclusive jurisdiction of the English courts.

7.2   If any provision of this agreement is found to be invalid by any court having competent jurisdiction, the invalidity of such provision shall not affect the validity of the remaining provisions of this agreement, which shall remain in full force and effect.

7.3   No waiver of any term of this agreement shall be deemed a further or continuing waiver of such term or any other term.

7.4   This agreement constitutes the entire agreement between you and RealVNC.

Radio Frequency Energy

A Category 5 (or better) twisted pair cable must be used to connect the Wizard IP unit in order to maintain compliance with radio frequency energy emission regulations and ensure a suitably high level of immunity to electromagnetic disturbances.

All other interface cables used with this equipment must be shielded in order to maintain compliance with radio frequency energy emission regulations and ensure a suitably high level of immunity to electromagnetic disturbances.

European EMC directive 89/336/EEC

This equipment has been tested and found to comply with the limits for a class A computing device in accordance with the specifications in the European standard EN55022. These limits are designed to provide reasonable protection against harmful interference. This equipment generates, uses and can radiate radio frequency energy and if not installed and used in accordance with the instructions may cause harmful interference to radio or television reception. However, there is no guarantee that harmful interference will not occur in a particular installation. If this equipment does cause interference to radio or television reception, which can be determined by turning the equipment on and off, the user is encouraged to correct the interference with one or more of the following measures: (a) Reorient or relocate the receiving antenna. (b) Increase the separation between the equipment and the receiver. (c) Connect the equipment to an outlet on a circuit different from that to which the receiver is connected. (d) Consult the supplier or an experienced radio/TV technician for help.

FCC Compliance Statement (United States)

This equipment generates, uses and can radiate radio frequency energy and if not installed and used properly, that is, in strict accordance with the manufacturer's instructions, may cause interference to radio communication. It has been tested and found to comply with the limits for a class A computing device in accordance with the specifications in Subpart J of part 15 of FCC rules, which are designed to provide reasonable protection against such interference when the equipment is operated in a commercial environment. Operation of this equipment in a residential area may cause interference, in which case the user at his own expense will be required to take whatever measures may be necessary to correct the interference. Changes or modifications not expressly approved by the manufacturer could void the user's authority to operate the equipment.

Canadian Department of Communications RFI statement

This equipment does not exceed the class A limits for radio noise emissions from digital apparatus set out in the radio interference regulations of the Canadian Department of Communications.

Le présent appareil numérique n'émet pas de bruits radioélectriques dépassant les limites applicables aux appareils numériques de la classe A prescrites dans le règlement sur le brouillage radioélectriques publié par le ministère des Communications du Canada.

FCC requirements for telephone-line equipment

1 The Federal Communications Commission (FCC) has established rules which permit this device to be directly connected to the telephone network with standardized jacks. This equipment should not be used on party lines or coin lines.

2 If this device is malfunctioning, it may also be causing harm to the telephone network; this device should be disconnected until the source of the problem can be determined and until the repair has been made. If this is not done, the telephone company may temporarily disconnect service.

3 If you have problems with your telephone equipment after installing this device, disconnect this device from the line to see if it is causing the problem. If it is, contact your supplier or an authorized agent.

4 The telephone company may make changes in its technical operations and procedures. If any such changes affect the compatibility or use of this device, the telephone company is required to give adequate notice of the changes.

5 If the telephone company requests information on what equipment is connected to their lines, inform them of:

   a The telephone number that this unit is connected to.

   b The ringer equivalence number.

   c The USOC jack required: RJ-11C.

   d The FCC registration number.

   Items (b) and (d) can be found on the unit's FCC label. The ringer equivalence number (REN) is used to determine how many devices can be connected to your telephone line. In most areas, the sum of the RENs of all devices on any one line should not exceed five (5.0). If too many devices are attached, they may not ring properly.

6 In the event of an equipment malfunction, all repairs should be performed by your supplier or an authorized agent. It is the responsibility of users requiring service to report the need for service to the supplier or to an authorized agent.

Certification notice for equipment used in Canada

The Canadian Department of Communications label identifies certified equipment. This certification means that the equipment meets certain telecommunications-network protective, operation, and safety requirements.

The Department does not guarantee the equipment will operate to the user's satisfaction.

Before installing this equipment, users should ensure that it is permissible to be connected to the facilities of the local telecommunications company.

The equipment must also be installed using an acceptable method of connection. In some cases, the company's inside wiring associated with a single-line individual service may be extended by means of a certified connector assembly (extension cord). The customer should be aware that compliance with the above conditions may not prevent degradation of service in some situations.

Repairs to certified equipment should be made by an authorized Canadian maintenance facility—in this case, your supplier. Any repairs or alterations made by the user to this equipment, or equipment malfunctions, may give the telecommunications company cause to request the user to disconnect the equipment.

Users should ensure for their own protection that the electrical ground connections of the power utility, telephone lines, and internal metallic water pipe system, if present, are connected together. This precaution may be particularly important in rural areas.

CAUTION:

Users should not attempt to make such connections themselves, but should contact the appropriate electric inspection authority, or electrician, as appropriate.

The LOAD NUMBER (LN) assigned to each terminal device denotes the percentage of the total load to be connected to a telephone loop which is used by the device, to prevent overloading. The termination on a loop may consist of any combination of devices, subject only to the requirement that the total of the load numbers of all the devices does not exceed 100.

Normas Oficiales Mexicanas (NOM) electrical safety statement

Instrucciones de seguridad

1 Todas las instrucciones de seguridad y operación deberán ser leídas antes de que el aparato eléctrico sea operado.

2 Las instrucciones de seguridad y operación deberán ser guardadas para referencia futura.

3 Todas las advertencias en el aparato eléctrico y en sus instrucciones de operación deben ser respetadas.

4 Todas las instrucciones de operación y uso deben ser seguidas.

5 El aparato eléctrico no deberá ser usado cerca del agua—por ejemplo, cerca de la tina de baño, lavabo, sótano mojado o cerca de una alberca, etc.

6 El aparato eléctrico debe ser usado únicamente con carritos o pedestales que sean recomendados por el fabricante.

7 El aparato eléctrico debe ser montado a la pared o al techo sólo como sea recomendado por el fabricante.

8 Servicio—El usuario no debe intentar dar servicio al equipo eléctrico más allá a lo descrito en las instrucciones de operación. Todo otro servicio deberá ser referido a personal de servicio calificado.

9 El aparato eléctrico debe ser situado de tal manera que su posición no interfiera su uso. La colocación del aparato eléctrico sobre una cama, sofá, alfombra o superficie similar puede bloquea la ventilación, no se debe colocar en libreros o gabinetes que impidan el flujo de aire por los orificios de ventilación.

10 El equipo eléctrico deber ser situado fuera del alcance de fuentes de calor como radiadores, registros de calor, estufas u otros aparatos (incluyendo amplificadores) que producen calor.

11 El aparato eléctrico deberá ser connectado a una fuente de poder sólo del tipo descrito en el instructivo de operación, o como se indique en el aparato.

12 Precaución debe ser tomada de tal manera que la tierra fisica y la polarización del equipo no sea eliminada.

13 Los cables de la fuente de poder deben ser guiados de tal manera que no sean pisados ni pellizcados por objetos colocados sobre o contra ellos, poniendo particular atención a los contactos y receptáculos donde salen del aparato.

14 El equipo eléctrico debe ser limpiado únicamente de acuerdo a las recomendaciones del fabricante.

15 En caso de existir, una antena externa deberá ser localizada lejos de las lineas de energia.

16 El cable de corriente deberá ser desconectado del cuando el equipo no sea usado por un largo periodo de tiempo.

17 Cuidado debe ser tomado de tal manera que objectos liquidos no sean derramados sobre la cubierta u orificios de ventilación.

18 Servicio por personal calificado deberá ser provisto cuando:

A: El cable de poder o el contacto ha sido dañado; u

B: Objetos han caído o líquido ha sido derramado dentro del aparato; o

C: El aparato ha sido expuesto a la lluvia; o

D: El aparato parece no operar normalmente o muestra un cambio en su desempeño; o

E: El aparato ha sido tirado o su cubierta ha sido dañada.

INSTALLATION

CONFIGURATION

OPERATION

FURTHER INFORMATION

INDEX

Index

A

Access control
  configuration 52
  mask calculation 59
Access mode
  shared & private 28
Account
  creation for users 48
Address
  explanation 57
Addressing
  DNS 18
  network issues 18
  power switch boxes 10
Admin password
  initial setup 12
  local setting 36
Advanced unit configuration
    50
Artifacts
  on screen 26
Auto calibrate 28
Auto select 41,46

B

Baud rate
  local setting 38
  remote setting 53
Binary
  net masks 58
Brackets 5
  fitting 6
Browser
  connection 25

C

Cables 5
Cable specifications
    57,61,62,63
Calibrate
  mouse 28
  screen 28
Calibrate all
  video settings 31
CATx switches
  threshold 31
Clear IP access control
  local setting 37
Client IP
  local setting 38
Colour level 41
COM1
  baud rate 53
  connection 9
COM2
  baud rate 53
  connection 10
Configuration
  initial steps 11
  remote 16
Configuration switches 4
Connections
  host computer 7
  ISDN 9
  keyboard 8
  KVM switch 7
  local 23
  modem 9
  monitor 8
  mouse 8
  network port 8
  power supply 9
  remote 24

Connector specifications 61
Controls
  viewer options 29
Control menus
  for local connection 35
  for remote connection 26,47
Control strings
  power switching 20

D

Daisy chain cable 61
Date
  local setting 36
  remote setting 49
DHCP
  discovering allocations 18
  during initial setup 12
  local setting 22,37
  remote setting 51
Dial up
  connection 32
DNS addressing 18

E

Encryption key 12
Encryption settings 13
  viewer 33
End user licence 65

F

Firewall 17
Firmware
  current version 49
  upgrade 22
Flash upgrade 22
Force encryption 36
Full screen mode
  escape from (F8) 26

G

Gateway
  local setting 22,37
  remote setting 51

H

Hextile 41,46
Hosts
  changing between 26,27
  configuration 54
Host computer
  connecting 7
  power switching setup 20
Host configuration 54
Host selection 27
Hotkeys
  to access menus 35
Hotkey sequences 55
  codes and macros 62
Hot keys
  changing 36
  remote setting 49
HTTP port
  initial setup 12
  local setting 37
  remote setting 51
  when altered 17

I

Identities
  VNC Viewer 44
IEC power lead 9
Indicators 4
Initialise button 53
Initialize port
  local setting 38

Initial configuration 11
Init string
  local setting 38
IntelliMouse 14
IP access control 51,52
  calculating mask 59
IP address
  explanation 57
  local setting 22,37
  remote setting 51
IP gateway 51
IP network mask 51
IP network port 4
  connecting 8
ISDN
  connecting 9
  dial up link 32

K

Keyboard codes
  sending 30
Keyboard Layout
  remote setting 49
Keyboard layout
  local setting 36
KVMADMIN utility 21
KVM console 4
KVM switch
  connecting 7

L

Local connection 23
local control menus 35
Local network
  connection 17
Logging 56
Log on 25

M

MAC address 37,51
Mask
  explanation 57
  for IP access control 59
Menus
  local 35
  remote 47
Menu bar
  viewer window 26
Menu key
  changing 42
Modem
  connecting 9
  dial up link 32
Modem configuration 38
Modem port 4
Mounting 6
Mouse
  calibration 28
  control 29
  pointers 27
  restoration 13,14
  resync 28,29

N

Networking issues 17
Network configuration 37,51
Network port
  connecting 8
Net mask 22,37
  explanation 57

O

Octets
  ip address 57

P

Password
  admin - setting 36
  initial setup 12
  remote logon 25
  setting for users 48
  unknown 15
Port number
  entering 32
Power control port 4
  connecting 10
Power strings
  for switching 20
Power supply
  connecting 9
Power switching
  addressing 10
  configuration 20
  on & off select 28
  user permissions 48
PPP client IP address 53
PPP server IP address 53
Preferred encoding 41
Private
  access mode 28

R

Rack mounting 6
Raw 41,46
Refresh screen 29
Remote configuration 16
  advanced unit configuration
    50
  host configuration 54
  logging and status 56
  main menu 47
  network configuration 51
  serial port configuration 53
  setting IP access control 52
  unit configuration 49
  user accounts 48

Remote connection 24
Reset
  to factory defaults 15
Reset configuration 39
Restore Defaults
  local setting 38
Resync mouse 29
RJ9 connector 10
Router 17

S

Safety information 64
Scaling
  VNC Viewer 43
Screen
  best resolution 26
  calibration 28
  navigation 26
  refresh 29
Screensaver
  local setting 36
  remote setting 49
Security
  ensuring 19
Serial port
  modem connection 9
Serial port configuration 53
Server
  configuration 54
Server IP
  local setting 38
Setup procedure
  local setup 11
  remote setup 16
Shared
  access mode 28
Single mouse mode 27,29
Slow connections
  optimising for 26
Supplied items 5

T

Threshold
  adjustment 31
Time
  local setting 36
  remote setting 49
Troubleshooting 34

U

Unit configuration 36,49
Unit name
  local setting 36
  remote setting 49
Upgrade
  firmware 22
Username
  initial setup 13
  remote logon 25
User accounts 48
Use DHCP
  local setting 22,37

V

Video modes 63
Video settings 30
Viewer window 26
VNC port
  initial setup 12
  local setting 37
  remote setting 51
  when altered 17
VNC viewer
  configuration menus 47
  connection 25
  connection options 41
  download 32
  window options 45

W

Warranty 64
Web browser
  connection 25
  viewer options 46

Z

ZRLE 41,46

®

INSTALLATION

CONFIGURATION

OPERATION

FURTHER
INFORMATION

INDEX

BlackBox subsidiary contact details

Country	Web Site/Email	Phone	Fax
United States	www.blackbox.com	724-746-5500	724-746-0746
Austria	www.black-box.at support@black-box.at	+43 1 256 98 56	+43 1 256 98 56
Belgium	www.blackbox.be support.nederlands@blackbox.be support.french@blackbox.be support.english@blackbox.be	+32 2 725 85 50	+32 2 725 92 12
Denmark	www.blackbox.dk blackbox@blackbox.dk	+32 2 725 85 50	+32 2 725 92 12
Finland	www.blackbox.fi tuki@blackbox.fi	+35 201 888 800	+35 201 888 808
France	www.blackbox.fr tech@blackbox.fr	+33 1 45 606 717	+33 1 45 606 747
Germany	www.black-box.de techsupp@black-box.de	+49 811 5541 110	+49 811 5541 499
Italy	www.blackbox.it supporto.tecnico@blackbox.it	+39 02 27 404 700	+39 02 27 400 219
Netherlands	www.blackbox.nl techsupport@blackbox.nl	+31 30 241 7799	+31 30 241 4746
Norway	www.blackboxnorge.no support@blackboxnorge.no	+47 55 300 710	+47 55 300 701
Spain	www.blackbox.es tecnico@blackbox.es	+34 9162590732	+34 916239784
Sweden	www.blackboxab.se support@blackboxab.se	+46 8 44 55 890	+46 08 38 04 30
Switzerland	www.black-box.ch support@black-box.ch	+41 55 451 70 71	+41 55 451 70 75
UK	www.blackbox.co.uk techhelp@blackbox.co.uk	+44 118 965 6000	+44 118 965 6001
Ireland	www.blackbox.co.uk techhelp@blackbox.co.uk	+353 1 662 2466	+353 1 662 2477